

AD-A155 635


NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS  
INDIAN LAKE DAM (MA 0..(U) CORPS OF ENGINEERS WALTHAM  
MA NEW ENGLAND DIV DEC 79


1/2

UNCLASSIFIED

F/G 13/13

NL





MICROCOPY RESOLUTION TEST CHART  
NATIONAL BUREAU OF STANDARDS-1963-A

AD-A155 635

CONNECTICUT RIVER BASIN  
BECKET, MASSACHUSETTS

INDIAN LAKE DAM  
MA 01051

PHASE I INSPECTION REPORT  
NATIONAL DAM INSPECTION PROGRAM

DTIC  
JUN 27 1985  
G



DEPARTMENT OF THE ARMY  
NEW ENGLAND DIVISION, CORPS OF ENGINEERS  
WALTHAM, MASS. 02154

DECEMBER 1979

DISTRIBUTION STATEMENT A  
Approved for public release  
Distribution Unlimited

85 06 6 0 28

## **DISCLAIMER NOTICE**

**THIS DOCUMENT IS BEST QUALITY  
PRACTICABLE. THE COPY FURNISHED  
TO DTIC CONTAINED A SIGNIFICANT  
NUMBER OF PAGES WHICH DO NOT  
REPRODUCE LEGIBLY.**

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER MA 01051	2. GOVT ACCESSION NO. AD-A155635	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) Indian Lake Dam		5. TYPE OF REPORT & PERIOD COVERED INSPECTION REPORT
NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS		6. PERFORMING ORG. REPORT NUMBER
7. AUTHOR(s) U.S. ARMY CORPS OF ENGINEERS NEW ENGLAND DIVISION		8. CONTRACT OR GRANT NUMBER(s)
9. PERFORMING ORGANIZATION NAME AND ADDRESS		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS
11. CONTROLLING OFFICE NAME AND ADDRESS DEPT. OF THE ARMY, CORPS OF ENGINEERS NEW ENGLAND DIVISION, NEDED 424 TRAPELO ROAD, WALTHAM, MA. 02254		12. REPORT DATE December 1979
		13. NUMBER OF PAGES 85
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)		15. SECURITY CLASS. (of this report) UNCLASSIFIED
		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
16. DISTRIBUTION STATEMENT (of this Report) APPROVAL FOR PUBLIC RELEASE: DISTRIBUTION UNLIMITED		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES Cover program reads: Phase I Inspection Report, National Dam Inspection Program; however, the official title of the program is: National Program for Inspection of Non-Federal Dams; use cover date for date of report.		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) DAMS, INSPECTION, DAM SAFETY, Connecticut River Basin Becket, Massachusetts Spark Brook		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) The dam is an earth embankment about 460 ft. long with a height of about 15 ft. above the brook channel. The embankment is in fair condition. It is small in size with a hazard potential of high. Some leakage is apparently occurring under the embankment, but does not appear to be hazardous.		



DEPARTMENT OF THE ARMY  
NEW ENGLAND DIVISION, CORPS OF ENGINEERS  
424 TRAPELO ROAD  
WALTHAM, MASSACHUSETTS 02154

REPLY TO  
ATTENTION OF:  
NEDED

AUG 11 1960

Honorable Edward J. King  
Governor of the Commonwealth of  
Massachusetts  
State House  
Boston, Massachusetts 02133

Dear Governor King:

Inclosed is a copy of the Indian Lake Dam Phase I Inspection Report, which was prepared under the National Program for Inspection of Non-Federal Dams. This report is presented for your use and is based upon a visual inspection, a review of the past performance and a brief hydrological study of the dam. A brief assessment is included at the beginning of the report. I have approved the report and support the findings and recommendations described in Section 7 and ask that you keep me informed of the actions taken to implement them. This follow-up action is a vitally important part of this program.

A copy of this report has been forwarded to the Department of Environmental Quality Engineering, the cooperating agency for the Commonwealth of Massachusetts. In addition, a copy of the report has also been furnished the owner, Community Savings Bank, 200 Main Street, Holyoke, Massachusetts 01040.

Copies of this report will be made available to the public, upon request, by this office under the Freedom of Information Act. In the case of this report the release date will be thirty days from the date of this letter.

I wish to take this opportunity to thank you and the Department of Environmental Quality Engineering for your cooperation in carrying out this program.

Sincerely,

*Max B. Scheider*  
MAX B. SCHEIDER

Colonel, Corps of Engineers  
Division Engineer

Incl  
As stated

INDIAN LAKE DAM  
MA 01051



Accession For		
NTIS GRA&I	<input checked="checked" type="checkbox"/>	
DTIC TAB	<input type="checkbox"/>	
Unannounced	<input type="checkbox"/>	
Justification		
By		
Distribution/		
Availability Codes		
Dist	Avail and/or Special	
A/1		23

CONNECTICUT RIVER BASIN  
BECKET, MASSACHUSETTS

PHASE I INSPECTION REPORT  
NATIONAL DAM INSPECTION PROGRAM

NATIONAL DAM INSPECTION PROGRAM  
PHASE I INSPECTION REPORT

Identification No.: MA 01051  
Mass. DPW No.: 1-2-22-17  
Name of Dam: Indian Lake Dam  
Town: Becket  
County and State: Berkshire County, Massachusetts  
Stream: Spark Brook  
Date of Inspection: October 31, 1979

BRIEF ASSESSMENT

Indian Lake Dam is located on Spark Brook, a tributary of Walker Brook which joins the West Branch of the Westfield River at Chester, Massachusetts. The dam is an earth embankment about 460 feet long with a height of about 15 feet above the brook channel. Near the center of the embankment is a reinforced concrete gravity wall spillway and control structure. The spillway is a free overfall straight drop type with a reinforced concrete, stone lined stilling basin and outfall channel, and provisions for flashboards or stop logs on the crest. A 30 inch square reservoir drain with hand operated sluice gate is also provided in the spillway structure.


The dam is owned by Community Savings Bank, Holyoke, Massachusetts. The dam was designed by Barnes & Jarnis Engineers, Inc., Boston, Massachusetts. The dam was built in 1974/1975 for recreational purposes. It has a tributary drainage area of 1.32 square miles and a maximum design storage capacity of 621 acre-feet.

The embankment is in FAIR condition. The embankment is not at design height and downstream embankment protection has not been provided. The spillway is in FAIR condition. The spillway structure shows signs of poor workmanship and deficiencies which could eventually create hazards. Some leakage is apparently occurring under the embankment, but does not appear to be hazardous.

The preliminary hydrologic and hydraulic tests for this SMALL size, HIGH hazard class dam indicate the spillway is adequate if properly operated. Due to the potential hazard to downstream highways and development in the Town of Chester, a one-half Probable Maximum Flood ( $\frac{1}{2}$  PMF) was developed to test spillway capacity. The area tributary to the dam site is gently rolling upland about 95% covered with good forest and with a considerable area of swamp just above the reservoir to retard and reduce runoff. The rolling terrain curve for maximum probable flood was used and extrapolated to about 1.3 square miles. This indicated a peak flood flow of about 1125 cfs per square mile, or 1,300 cfs on this drainage area. Routing this flood flow through the reservoir starting at normal water level, but assuming that the flashboards would go out, the spillway would carry the estimated maximum outflow of 750 cfs with about 1.2 feet freeboard if the embankment is completed to design height.



It is recommended that the embankment be brought to design height and riprap placed on the downstream slope within the next year. Stop log guides should be modified so that only thinner flashboards can be inserted and so that the height above the concrete crest cannot exceed a pre-determined height. The left embankment drain should be inspected by excavating at various points along its length to ascertain the cause of its apparent malfunctioning. Inspection and maintenance should be performed on a regular basis at least annually.



*John W. Powers*  
*Sanitary*  
John W. Powers  
Massachusetts Registration 23106

This Phase I Inspection Report on Indian Lake Dam has been reviewed by the undersigned Review Board members. In our opinion, the reported findings, conclusions, and recommendations are consistent with the Recommended Guidelines for Safety Inspection of Dams, and with good engineering judgment and practice, and is hereby submitted for approval.

*Richard J. DiBuono*

RICHARD DIBUONO, MEMBER  
Water Control Branch  
Engineering Division

*Aramast Mahtesian*

ARAMAST MAHTESIAN, MEMBER  
Geotechnical Engineering Branch  
Engineering Division

*Carney M. Terzian*

CARNEY M. TERZIAN, CHAIRMAN  
Design Branch  
Engineering Division

APPROVAL RECOMMENDED:

*Joe B. Fryar*

JOE B. FRYAR  
Chief, Engineering Division

## PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dam for Phase I Investigations. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D.C. 20314. The purpose of a Phase I Investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigation, and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I investigation; however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. In cases where the reservoir was lowered or drained prior to inspection, such action, while improving the stability and safety of the dam, removes the normal load on the structure and may obscure certain conditions which might otherwise be detectable if inspected under the normal operating environmental of the structure.

It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through continued care and inspection can there be any chance that unsafe conditions be detected.

Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established Guidelines, the Spillway Test flood is based on the estimated "Probable Maximum Flood" for the region (greatest reasonably possible storm runoff), or fractions thereof. Because of the magnitude and rarity of such a storm event, a finding that a spillway will not pass the test flood should not be interpreted as necessarily posing a highly inadequate condition. The test flood provides a measure of relative spillway capacity and serves as an aide in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition and the downstream damage potential.

The Phase I Investigation does not include an assessment of the need for fences, gates, no-trespassing signs, repairs to existing fences and railings and other items which may be needed to minimize trespass and provide greater security for the facility and safety to the public. An evaluation of the project for compliance with OSHA rules and regulations is also excluded.

## TABLE OF CONTENTS

<u>Section</u>	<u>Page</u>
LETTER OF TRANSMITTAL	
BRIEF ASSESSMENT	
REVIEW BOARD SIGNATURE SHEET	
PREFACE	i
TABLE OF CONTENTS	ii-iv
OVERVIEW PHOTO	v
LOCUS PLAN 1	vi
LOCUS PLAN 2	vii

## REPORT

1. PROJECT INFORMATION	
1.1 General	1-1
a. Authority	1-1
b. Purpose of Inspection	1-1
1.2 Description of Project	1-1
a. Location	1-1
b. Description of Dam and Appurtenances	1-2
1) Embankment	1-2
2) Spillway	1-2
c. Size Classification	1-3
d. Hazard Classification	1-3
e. Ownership	1-3
f. Operator	1-4
g. Purpose of Dam	1-4
h. Design and Construction History	1-4
i. Normal Operational Procedure	1-5
1.3 Pertinent Data	1-5
2. ENGINEERING DATA	
2.1 Design Data	2-1
2.2 Construction Data	2-1
2.3 Operation Data	2-1
2.4 Evaluation of Data	2-1

<u>Section</u>	<u>Page</u>
3. VISUAL INSPECTION	
3.1 Findings	3-1
a. General	3-1
b. Dam	3-1
c. Appurtenant Structures	3-1
d. Reservoir Area	3-1
e. Downstream Channel	3-2
3.2 Evaluation	3-2
4. OPERATIONAL AND MAINTENANCE PROCEDURES	
4.1 Operational Procedures	4-1
4.2 Maintenance Procedures	4-1
4.3 Evaluation	4-1
5. EVALUATION OF HYDRAULIC/HYDROLOGIC FEATURES	
5.1 General	5-1
5.2 Design Data	5-1
5.3 Experience Data	5-2
5.4 Test Flood Analysis	5-2
5.5 Dam Failure Analysis	5-3
6. EVALUATION OF STRUCTURAL STABILITY	
6.1 Visual Observation	6-1
6.2 Design and Construction Data	6-1
6.3 Post-Construction Changes	6-1
6.4 Seismic Stability	6-1
7. ASSESSMENT, RECOMMENDATIONS AND REMEDIAL MEASURES	
7.1 Dam Assessment	7-1
a. Condition	7-1
b. Adequacy of Information	7-1
c. Urgency	7-1

<u>Section</u>	<u>Page</u>
7. ASSESSMENT, RECOMMENDATIONS AND REMEDIAL MEASURES (continued)	
7.2 Recommendations	7-1
7.3 Remedial Measures	7-2
7.4 Alternatives	7-2

#### APPENDICIES

APPENDIX A - INSPECTION CHECKLIST


APPENDIX B - ENGINEERING DATA

APPENDIX C - PHOTOGRAPHS

APPENDIX D - HYDROLOGIC AND HYDRAULIC  
COMPUTATIONS

APPENDIX E - INFORMATION AS CONTAINED IN THE  
NATIONAL INVENTORY OF DAMS





**TIGHE & BOND / SCI**  
**CONSULTING ENGINEERS**  
 EASTHAMPTON, MASS.

**U.S. ARMY ENGINEER DIV. NEW ENGLAND**  
**CORPS OF ENGINEERS**  
 WALTHAM, MASS.

**NATIONAL PROGRAM OF INSPECTION OF NON-FED. DAMS**

## LOCUS PLAN I


**INDIAN LAKE DAM (MA 01051)**  
**BERKSHIRE COUNTY**

**BECKET**  
**MASSACHUSETTS**

**SCALE: AS NOTED**

**DATE: DECEMBER 1979**





- SCALE -

1000' 0' 1000' 2000' 3000' 4000'

FROM USGS OTIS  
BECKET  
CHESTER

TIGHE & BOND / SCI  
CONSULTING ENGINEERS  
EASTHAMPTON, MASS.

U.S. ARMY ENGINEER DIV. NEW ENGLAND  
CORPS OF ENGINEERS  
WALTHAM, MASS.

NATIONAL PROGRAM OF INSPECTION OF NON-FED. DAMS

## LOCUS PLAN 2

INDIAN LAKE DAM (MA 01051)  
BERKSHIRE COUNTY

BECKET  
MASSACHUSETTS

SCALE: AS NOTED

DATE: DECEMBER 1979

# NATIONAL DAM INSPECTION PROGRAM

## PHASE I INSPECTION REPORT

### INDIAN LAKE DAM

#### SECTION 1

#### PROJECT INFORMATION

##### 1.1 General

###### (a) Authority

Public Law 92-367, August 8, 1972, authorized the Secretary of the Army, through the Corps of Engineers, to initiate a National Program of Dam Inspection throughout the United States. The New England Division of the Corps of Engineers has been assigned the responsibility of supervising the inspection of dams within the New England Region. Tighe & Bond/SCI has been retained by the New England Division to inspect and report on selected dams in Massachusetts. Authorization and notice to proceed were issued to Tighe & Bond/SCI under a letter of October 24, 1979 from Colonel William E. Hodgson, Jr. Inc., Corps of Engineers. Contract No. DACW 33-80-C-0005 has been assigned by the Corps of Engineers for this work.

###### (b) Purpose

- 1) Perform technical inspection and evaluation of non-federal dams to identify conditions which threaten the public safety and thus permit correction in a timely manner by non-federal interests.
- 2) Encourage and prepare the states to initiate quickly effective dam safety programs for non-federal dams.
- 3) Update, verify, and complete the National Inventory of Dams.

###### (c) Scope

The program provides for the inspection of non-federal dams in the high hazard potential category based upon location of the dams, and those dams in the significant hazard potential category believed to represent an immediate danger based on condition of the dams.

##### 1.2 Description of Project

###### (a) Location

Indian Lake dam is located on Spark Brook about 8,000 feet upstream of its confluence with Walker Brook which flows into the

West Branch of the Westfield River at Chester, Massachusetts about 3.8 miles downstream from the Spark Brook confluence. This dam is about 600 feet to the west off Bonny Rigg Hill Road at a point about 1.1 miles south of U.S. Route 20 at Bonny Rigg Corners, which is about 4.6 miles west along Route 20 from Chester, Massachusetts. The dam site is shown on the U.S.G.S. Otis, Mass. quadrangle at longitude N42°-14'-57" and latitude W73°-01'-27". (See locus plans)

(b) Description of Dam and Appurtenances

The dam consists of an uncompleted earth embankment about 460 feet long with impervious seal at upstream toe and height above streambed of about 15 feet. Near the center of the embankment is a reinforced concrete spillway and control structure.

1) Embankment

The embankment is a zoned compacted earthfill embankment. The principal embankment material used for impervious and toe seal is local glacial till placed wet of optimum. Clean sandy gravel was used for foundation replacement of peat in the swamp area, for bedding for rock riprap, and for embankment crest. Random granular borrow was used to build the downstream shell. Heavy dumped rock riprap provides upstream slope protection from below minimum water level to top of embankment. Loam to finish and protect the top of the embankment and the downstream slope is stockpiled on the downstream slope but has not been spread and seeded. Peastone pockets have been provided around the 6" ACCMP foundation drains. The embankment is founded on very firm glacial till.

The top of the embankment is about 14 feet wide but has not been completed to full height; it is about 1.1 feet below spillway abutment top for about 200 feet of the embankment length. Embankment side slopes, both upstream and downstream, are 2½ horizontal to 1 vertical. In areas where peat was removed, it was replaced with gravel and an impervious zone seal was placed upstream of the gravel foundation extending from the glacial till embankment body down to the till foundation and as much as 18 feet wide.

The right or southeast embankment crosses a low ridge which has been excavated to assure that surface drainage from the downstream face will flow to the brook some distance from the embankment toe.

2) Spillway

The spillway and reservoir drain are located in a reinforced concrete structure near the right or southeast side of the valley bottom. The reservoir drain is a 30 in. x 30 in. sluice way at the left, northwesterly, bay of the spillway. It

is closed by a manually operated sluice gate with invert at about the level of the old stream bed.

The spillway is a broad crested free overfall type with straight drop to the reinforced concrete stilling basin which is lined with heavy riprap rock. The spillway wall is vertical between piers and provides three 5'-4" clear width bays. Above the vertical faced reinforced concrete spillway crest the piers are fitted with steel stop log channels 4 3/4 inches wide and 2 inches deep.

Provisions have been made for a steel stringer and grating deck bridge for access to the stop logs. Also, provisions have been made for fencing on the top of the spillway side walls and wing walls. Neither the bridge nor the fence have been installed.

The entrance channel in front of the spillway base slab between and in front of the wing walls is lined with riprap. The outlet end of the stilling basin has a slotted end sill to contain riprap fill and assure a hydraulic jump before outflow enters the outlet channel. Inlet wing walls are at 60° to spillway channel axis; and outlet wing walls at 45° to channel axis. Spillway side walls and wing walls are cantilever retaining walls without weep holes.

(c) Size Classification

Dam size based on height of embankment is SMALL. Dam size based on maximum impoundment at design top of dam of 621 acre-feet is SMALL. The dam size rated by the Corps of Engineers Guidelines is SMALL.

(d) Hazard Classification

This dam, rated by the Corps of Engineers Guidelines, is classed as a HIGH hazard dam due to the potential loss of many lives in a seasonally densely populated campground and potential destruction of at least two year-round residences downstream of the dam along Walker Brook.

(e) Ownership

The present owner of the dam is:

Community Savings Bank  
200 Main Street  
Holyoke, Massachusetts 01040  
Tel.: 413-536-7220

The original owner and builder of the dam was:

Mr. James F. Hansman  
67 Harwich Road  
West Springfield, Massachusetts 01089

(f) Operator

No day to day operator is known. The contact person for the owner is Mr. Agostino J. Calheno, Assistant Vice President, Community Savings Bank, Tel.: 413-536-7220; night Tel.: 413-532-7765.

(g) Purpose of Dam

The dam was built to provide a recreation pond for a planned vacation development. The developer went bankrupt and neither the dam nor the development was completed. The development is not occupied and the pond is not actively used. However, the reservoir is at about design normal water level.

(h) Design and Construction History

The dam was designed by Barnes & Jarnis, Inc., Engineers, 61 Batterymarch Street, Boston, Massachusetts. Site survey and layout services were provided by Gordon .E. Ainsworth & Associates, Land Surveyors, South Deerfield, Massachusetts. Haley & Aldrich, Inc., Consulting Soils Engineers, Cambridge, Massachusetts provided soils engineering services. Preliminary soil borings were taken by C.L. Guild Drilling and Boring Co., Inc., Braintree, Mass.; soil test pits were excavated under the supervision of Haley & Aldrich.

General contractor for the construction of the dam embankment was Andrews Construction Co., Washington Road, Washington, Mass. Concrete spillway construction was by Western Massachusetts Engineering Company, Lee, Mass. Construction was carried out between October 1974 and October 1975.

Plans and specifications for the dam were reviewed and approved by the Massachusetts Department of Environmental Quality Engineering, Division of Waterways. Site inspections by Division of Waterways' personnel were carried out both during and after construction.

Construction started in October 1974, Spark Brook was diverted to the left, or northwest, and most of the right or southeast embankment was completed during that fall. Excavation and embankment construction were inspected by Haley & Aldrich personnel.

Spillway construction was completed before August 5, 1975 when embankment construction was resumed and Spark Brook was diverted through the reservoir drain in the spillway structure. Construction was halted due to lack of payments about October 6, 1975 with a number of items still incomplete. It appears that no further construction work on the dam has been accomplished since then.

i) Normal Operating Procedure

Normally the dam would require no operation. The spillway allows excess water to overflow when fitted with proper flashboards. The normal pool level will be maintained by stream inflow with excess discharging over the spillway. In the event of excessive inflow, the flashboards should wash out, automatically increasing spillway capacity for emergency conditions.

1.3 Pertinent Data

(a) Drainage Area

The drainage area of this dam covers about 1.3 square miles. It is made up of rolling well forested uplands above 1400 feet elevation with few clearings. About 3,800 feet of the Massachusetts Turnpike, Route I-90, abuts or crosses the watershed. There are about 41 acres of low level swamps making up about 5 percent of the watershed. Much of this is low in the watershed, only slightly above maximum reservoir elevation.

(b) Discharge at Dam Site

1) Outlet Works

Normal discharge at the site is over the spillway crest. The crest of the reinforced concrete spillway wall is at elevation 1,473.0 MSL. The crest is fitted to allow installation of stop logs or flashboards to elevation 1,478.5 NGVD. The top of the reinforced concrete spillway sidewall is 1,480.0 NGVD. This is the same elevation as the design crest of the embankment. The top of the embankment is now at elevation 1,478.9 NGVD.

A reservoir drain is also located in the concrete spillway structure. It is a 30 in. x 30 in. sluice way with a manually operated sluice gate. Sluice gate invert is 1465.6 NGVD. Maximum drain capacity is about 127 cfs.

- 1) Outlet works (reservoir drain) - 30" x 30"  
Sluice way: Discharge capacity - 120 cfs

- 2) Maximum Known Flood at dam site - Unknown

2) Maximum Known Flood

Maximum known flood at the dam site is of unknown magnitude.

3) Ungated Spillway Capacity at Top of Dam

The capacity of the spillway above the normal elevation of the stop logs (1,475.0 feet NGVD) to the top of the

existing embankment (1,478.9 feet NGVD) is 410 cfs.

The capacity of the spillway above the normal elevation of the stop logs (1,475.0 feet MSL, NGVD) to the top of the embankment as designed (1,480.0 feet NGVD) is 595 cfs.

4) Ungated Spillway Capacity at Test Flood

The capacity of the spillway above the normal elevation of the stop logs (1475.0 feet MSL, NGVD) to the test flood elevation (1478.8 feet MSL, NGVD) is 395 cfs.

5) Gated Spillway Capacity at Normal Pool

The capacity of the spillway with no stop logs (1,473.0 feet MSL, NGVD) and embankment at present elevation (1,478.9 feet NGVD) is 765 cfs.

The capacity of the spillway with no stop logs (1,473.0 feet MSL, NGVD) and embankment at design elevation (1,480.0 feet NGVD) is 987 cfs.

6) Gated Spillway Capacity at Test Flood

The capacity of the spillway with no stop logs (1473.0 feet MSL, NGVD) at the test flood elevation (1478.8 feet MSL, NGVD) is 750 cfs.

7) Total Spillway Capacity at Test Flood

The total spillway capacity at test flood (1,478.8 feet MSL, NGVD) with no flashboards on the fixed crest (1,473.0 feet MSL, NGVD) is 750 cfs.

8) Total Project Discharge at Top of Dam

Total project discharge with no flashboards above spillway fixed crest elevation (1,473.0 feet MSL, NGVD), embankment top at present elevation (1,478.9 feet MSL, NGVD), and reservoir drain open is 886 cfs.

Total project discharge with no flashboards above spillway fixed crest elevation (1,473.0 feet NGVD), embankment at design height (1,480.0 feet NGVD) and reservoir drain open is 1,114 cfs.

9) Total Project Discharge at Test Flood

Total project discharge with no flashboards above spillway fixed crest elevation (1,473.0 feet NGVD), reservoir drain open and pond at test flood elevation (1478.8 feet NGVD) is 870 cfs.

(c) Elevation (feet above MSL, NGVD)

- 1) Streambed at toe of dam: 1465±
- 2) Bottom of cutoff: 1457±
- 3) Maximum tailwater: Unknown
- 4) Design Recreation pool: 1,475.0
- 5) Full flood control pool: N/A
- 6) Spillway crest:
  - a) Pond drain inlet: 1,465.6
  - b) Fixed concrete spillway: 1,473.0
  - c) Stop log slot top: 1,478.5
- 7) Design surcharge: 1,477
- 8)
  - a) Top of dam designed: 1,480.0
  - b) Top of dam as found: 1,478.9
- 9) Test flood surcharge: 1,478.8

(d) Reservoir (Length in feet)

1. Design recreation pool: 2,250'
2. Flood control pool: Not applicable
3. Spillway crest pool: 2,000'
4. Actual Top of Dam: 2,350'
5. Design Top of Dam: 2380
5. Test flood surcharge: 2,350'

(e) Storage (acre-feet)

1. Design recreation pool: 256
2. Flood control pool: Not applicable
3. Spillway crest pool: 148
4. Test flood pool: 528



5. Actual Top of dam: 539
6. Design top of dam: 621

(f) Reservoir Surface (acres)

1. Design recreation pool: 62 acres
2. Flood control pool: Not applicable
3. Spillway crest pool: 46.2 acres
4. Test flood pool: 76 acres
5. Actual Top of dam: 76 acres
6. Design top of dam: 80 acres

(g) Dam

1. Type: Rolled earth embankment
2. Length: 460± ft.
3. Height: 15± ft.
4. Top width: 14 ft.
5. Side slopes: Upstream: 2.5 to 1  
downstream: 2.5 to 1
6. Zoning: Impervious glacial till core  
Sandy gravel foundation  
Random granular downstream shell  
Embankment drain of pea-gravel  
Riprap wave zone
7. Impervious core: Glacial till placed wet of optimum
8. Cutoff: Glacial till placed wet of optimum where gravel foundation was placed
9. Grout curtain: None

(h) Diversion and Regulating Tunnel

Not applicable

(i) Spillway

1. Type: Free overfall, reinforced concrete, broad crested weir

2. Length of weir: 16 feet
3. Crest elevation:
  1. No flashboard or stop log: elev. 1473.0 MSL
  2. Max. flashboard or stop log: elev. 1478.5 MSL
4. Gates: one 30" x 30" manual vertical lift drain sluice gate  
Stop logs: 3 bays 5'-4" clear opening by 5.50' high
5. Upstream channel: Riprap lined channel in reservoir for 50 feet beyond spillway foundation and wing walls
6. Downstream channel: Riprap lined reinforced concrete stilling basin and riprap lined transition to outflow channel

(j) Regulating Outlet

1. Flashboards regulate pond elevation
  - a. Invert: elev. 1,473.0 MSL
  - b. Size: Length: 3 bays of 5'-4"=16.0 feet total  
Height: up to 5.5'
  - c. Description: Steel edged slots 4 3/4 in. wide x 2 in. deep are provided in each pier from top of spillway crest (elev. 1,473.0 ft. MSL) to catwalk bridge seats (elev. 1,478.5 feet MSL)
  - d. Control mechanism: Flashboards or stop logs are placed in the slots across each spillway opening manually as desired. Removal is also manual
2. Reservoir drain:
  - a. Invert: elev. 1,465.6 MSL
  - b. Size: 30 in. x 30 in.
  - c. Description: Rodney Hunt HyQ rising stem sluice gate
  - d. Control mechanism: Hand operated geared lift stand on bracket on spillway wall

## SECTION 2 - ENGINEERING DATA

### 2.1 Design Data

To the best of our knowledge, design data in addition to that appearing on the plans and specifications furnished to the Massachusetts Division of Waterways is available at the offices of Barnes & Jarnis, Inc., Boston, Mass.

### 2.2 Construction Data

Construction inspection memos and reports are available at the offices of Haley & Aldrich, Inc., Cambridge, Mass.

"As built" plans are available from the Massachusetts Division of Waterways.

### 2.3 Operational Data

No operational data is available as the dam is self regulating.

### 2.4 Evaluation of Data

#### (a) Availability

Sufficient data is available to permit adequate evaluation of the dam when combined with visual inspection observations. Construction notes and memos did not reveal anything that would explain the lack of flow from the left foundation drain.

#### (b) Adequacy

There is sufficient design and construction data to permit an assessment of dam safety when combined with visual inspection observations, inspection reports and sound engineering judgment.

#### (c) Validity

Since visual inspection observations generally confirm the available data, it is considered valid.

## SECTION 3 - VISUAL INSPECTION

### 3.1 Findings

#### (a) General

Indian Lake Dam, MA 01051, was in FAIR condition at the time of the inspection.

#### (b) Dam

The earth embankment was found to be incomplete. The southeast (right) end is about 1.1 feet lower than top of spillway structure for a distance of about 117 feet. The northwest (left) end is about 1.1 feet lower than top of spillway structure and rises to a point about 52 ft. away where it is about 0.3 feet low.

Embankment top and downstream slope are unfinished and unprotected. Loam piles have been dumped at the toe of the slope. Minor erosion has developed on the downstream slope. Upstream riprap is satisfactory. Motorcycle tire tracks indicate trespass although there has been no serious damage.

Wet areas were found about 50 to 140 feet left of the spillway downstream from the toe of embankment. There were no "boil" spots or indications of "piping." The wet areas are considered to result from the use of gravel in the foundation beneath the impervious zone with only a thin cutoff seal at the upstream toe. The right foundation drain 30 minutes after being unclogged was flowing clear water - no sign of silt eroding into it. The left foundation drain was not flowing. There is no apparent reason why this drain should not have some flow since there was considerable wetness and minor surface ponding downstream from the toe of slope.

#### (c) Appurtenant Structures

The spillway structure was found to be in fair condition and functionally complete, although the spillway bridge and fencing have not been installed. The southeast side wall shows signs of a cold joint during concrete placing. There is efflorescence and seepage from this joint.

Stop logs were in place on the spillway crest raising the pool level to about 1.45 feet above the concrete crest. One base bolt for attaching the sluice gate lift stand to the base bracket was missing and one was corroded and obviously not of stainless steel construction.

#### (d) Reservoir Area

The reservoir shore appeared to be generally clear, gently sloping and stable. The reservoir is clear with little debris.

(e) Downstream Channel

The downstream channel is riprap lined for a short transition from the spillway and in satisfactory condition. The plunge pool of the spillway is rock lined and in good condition. The outflow channel is stable and satisfactory.

3.2 Evaluation

The dam is generally in FAIR condition. Deficiencies are as follows:

1. Embankment is 1.1' lower than design height.
2. Embankment top and downstream slope are unfinished; loam and seed were never placed.
3. The left foundation drain does not appear to be operating properly.
4. Access to the spillway for flashboard operation is incomplete.
5. The stop log guides will permit the use of heavy timber stop logs which would seriously reduce the capacity of the spillway if they did not washout in floods.
6. The stop log guides extend so high that spillway capacity can be dangerously inadequate if full height stop logs are installed.
7. The right foundation drain outlet was plugged at the time of our inspection; Tighe & Bond party unplugged this outlet.
8. Drain sluice gate lift stand mounting bolts are faulty.

## SECTION 4 - OPERATION AND MAINTENANCE PROCEDURES

### 4.1 Operation Procedures

#### (a) General

No written operational procedures are available for this dam. The dam is normally self regulating. The sluice gate on the pond drain is normally in the closed position and is not routinely operated.

#### (b) Description of Warning System in Effect

There is no written warning system in effect.

### 4.2 Maintenance Procedures

#### (a) General

To the best of our knowledge, no routine maintenance procedures are in effect for this dam. There are no regular maintenance inspections of this dam by qualified personnel.

#### (b) Operational Facilities

The pond drain sluice gate is not, to the best of our knowledge, routinely operated.

Flashboard maintenance and/or routine inspection is non-existent.

There are no other facilities which require operation.

### 4.3 Evaluation

The condition of the dam and its appurtenances at the time of our inspection indicate a lack of maintenance.

A regular maintenance program would assist the owners in assuring the long term safety of this dam.

A formal, written downstream emergency flood warning system should be developed for this dam.

## SECTION 5 - EVALUATION OF HYDRAULIC/ HYDROLOGIC FEATURES

### 5.1 General

Indian Lake Dam is located on Spark Brook about 8,000 feet (1.5 mi) above its confluence with Walker Brook at a point about 20,000 feet (3.8 mi) above the Village of Chester, Massachusetts at the confluence of Walker Brook and the West Branch of the Westfield River. The watershed above the dam has an area of about 1.3 square miles of gently rolling wooded uplands. The Massachusetts Turnpike crosses the upper end of the watershed. There are considerable swamp areas in the lower portions of the watershed above the reservoir.

Downstream of the dam the gradient of Spark Brook increases and it flows to Walker Brook. Walker Brook from the confluence with Spark Brook to the West Branch of the Westfield River parallels U.S. Route 20 through a steep, narrow gorge. The average slope of Spark Brook above the reservoir is about 95 feet per mile. The average slope of Spark Brook from the dam to Walker Brook is about 170 feet per mile. The average slope of Walker Brook below Spark Brook is about 160 feet per mile.

The spillway structure is constructed of reinforced concrete. The spillway is a free overfall concrete wall with a straight drop to a riprap lined reinforced concrete plunge basin.

### 5.2 Design Data

#### 1. Spillway design data (from construction plans):

Drainage area: 1.322 sq. mi. - 864 acres

Flood: August, 1955

Design Flood Reservoir Inflow : 1,415 cfs

Design Flood Outflow with flashboards at normal  
water level: 120 cfs

Maximum Water Level: 1,477.0 MSL

Reservoir Normal Water Level: 1,475.0 MSL

Storage Up To Normal Water Level: 255.8 ac. ft.

Storage Normal W.L. to Flood W.L.: 140.1 ac. ft.

Dam Top Elev.: 1,480.0 MSL

Freeboard Above Maximum W.L.: 3.0 ft.

This data indicates that a design storm of high intensity but short duration and moderate to low runoff volume was assumed.

### 5.3 Experience Data

Reference: U.S.G.S. Water Supply Paper 1420  
"Floods of August-October 1955"

Randomly selected data for locations in the same area as Indian Lake Dam were reviewed. Data is included in Appendix D.

Based on the 1955 flood report data, the design inflow peak and outflow peak are not unreasonable, but might be exceeded under some conditions.

### 5.4 Test Flood Analysis

The objective of the test flood analysis is to assess the capacity of the dam to safely pass a severe runoff event of a size commensurate with the size of the dam and the downstream hazard to life and property.

Guidelines for establishing a test flood are specified in "Recommended Guidelines" of the Corps of Engineers. Both the height of this dam (14.6 feet), which is less than 40 feet, and the storage volume at the top of the dam, (621 ac. ft.) which is less than 1,000 acre-feet, place this dam in the SMALL size class. The dam failure analysis indicated a potential for destruction of five year-round residences and much of a seasonally densely occupied campground with potential loss of more than a few lives making this a HIGH hazard class dam. Table 3 of the Corps of Engineers "Recommended Guidelines" recommends that the spillway test flood for a SMALL size, HIGH hazard class dam should be 1/2 probable maximum flood (PMF) to full PMF.

The 14.6 ft. height of this dam is substantially below the normal low limit of small dam size, indicating a test flood at low limit of recommended test flood range. The 621 acre feet maximum storage capacity is near the middle of the small size storage range indicating a test flood of about mid range. The watershed characteristics of good forest cover, low to moderate slopes in the "rolling" range, and swamps and low lands indicate a relatively slow and small storm runoff. For these reasons a test flood of 1/2 PMF reduced for watershed conditions has been adopted.

The spillway test flood was determined by extrapolating the "rolling" curve of "Maximum Probable Flood Peak Flow Rates" to the Indian Lake drainage area of 1.32 square miles. Half the discharge rate of 2250 cfs per square mile times 1.32 square miles area gives a peak flow of 1,485 cfs.

The PMF was reduced to allow for good forest cover, gently rolling slopes, and upstream swamps. 1266 cfs was taken as the peak inflow. Runoff volume was taken as  $19/2 = 9.5$  inches. This was routed through the reservoir starting with the reservoir at design normal water level (elev. 1,475.0 MSL). This limits reservoir storage for flood routing purposes to that above elev. 1,475.0 MSL.



Spillway capacity was calculated assuming behavior as a sharp edged rectangular weir with suppressed end contractions and of sufficient height to discharge the outflow flood above the crest elevation of 1,473.0 MSL. Reservoir drain sluice gate was assumed to be closed.

Though the first trial discharge height was above design top of dam, the final reservoir elevation was below design top of dam. Thus, it is appropriate to consider the routing characteristics using the discharge characteristics of the spillway only without introducing the altered characteristics of flow over the dam which would not occur under assumed conditions.

This PMF routing by the approximate methods suggested indicates that the PMF would fail to overtop the dam by about 1.2 feet if the embankment is at design height. Though the dam embankment is about 1.1 feet below design height, the dam as it stands would not be overtopped.

### 5.5 Dam Failure Analysis

The hazards and potential damages resulting from failure of Indian Lake Dam were evaluated based on conditions that would exist during a storm of the magnitude of the spillway test flood ( $\frac{1}{2}$  PMF) just prior to dam failure and when the dam failure flood wave occurred in addition to the prior flood on the drainage basin. The procedures of "Rule of Thumb Guidelines for Estimating Downstream Dam Failure Hydrographs" by New England Division, Corps of Engineers, were used.

The dam was assumed to fail at maximum stage determined by the spillway test flood analysis, elev. 1478.8 MSL, NGVD. This elevation was used to determine volume of the flood wave (528 acre-feet) and height from river bed to pool level at failure (13.2 feet). The length of the dam was taken along centerline of construction at mid height (elev. 1472.8 MSL, NGVD) between river bottom at dam and design top of dam from original ground surface at one end to original ground surface at the other end. Breach width was taken as 40 percent of mid height length less spillway width. This analysis gave a peak dam failure flood wave discharge of 7515 cfs.

River stages were determined for a typical section of each reach. The PMF was determined for the entire tributary drainage area above each point of analysis including the area tributary to the dam. River stage was determined for the flow resulting from  $\frac{1}{2}$  PMF on the tributary area below the dam plus flow at the dam; i.e. spillway flow for test flood or dam failure flow as attenuated along the river.

Damage at centers 1, 2, and 3 is likely to occur as a result of dam failure flow of 7515 cfs at river stages about four (4) feet higher than flood stage, but not due to the storm flood flow of about 750 cfs. Damage would probably amount to road washout, as there are no houses along the stream above damage center 4. At damage center 4 the road would probably be washed out as a result of the storm flood, but the nearby house is about eight (8) feet above the road and is not likely to be damaged by storm flood or dam failure. At damage center 5 the road and the nearby house both would be damaged by the storm without

dam failure. At Blandford Pond, damage center 6, the road and one house would probably be washed out by the storm flood. One additional nearby house would probably be damaged by dam failure.

At the Walker Island Campground, damage center 7, the main road, Route 20, would probably not be damaged but the local road and much of the campground and the permanent house would be damaged by the storm flood of 13,000 cfs and river stage about 7 feet deep. Little additional damage caused by dam failure flow of 18,400 cfs which would add about one (1) foot to river stage because camp sites are at two elevations separated by 10 to 15 ft. high river banks.

At damage center 8, near the town road bridge, the storm flood of about 14,000 cfs and ten (10) feet deep river stage, would probably wash out the road and two low lying houses. Other houses in the area are 10 to 15 feet above the road and would not be damaged by dam failure flow of 19,000 cfs which would add about two (2) feet to river stage.

Along Walker Brook in the Village of Chester, damage center 9, there are a number of houses within sight of the brook and more houses and business buildings along Main Street, Route 20, that would be damaged, along with road wash out by the storm flood flow of 14,000 cfs and river stage of about ten feet. Only a couple additional houses would be affected by dam failure flow of about 18,700 cfs which would add about half a foot to river stages. Other houses are higher up hillside above the river and roads.


Flood walls and channel improvements along the Westfield River are adequate for floods of about the magnitude of  $\frac{1}{2}$  PMF, 35,000 cfs and river stage of about 13.5 feet. The additional stage due to dam failure, about 4,700 cfs and about 0.7 feet, would probably not overtop the flood protection system in the Town.

In summary, it is estimated that storm damage along Spark Brook and adjacent areas of Walker Brook would not be serious but dam failure would probably cause wash out of the roads near bridges but little further damage, due to about two (2) foot higher river stages. Along lower reaches of Walker Brook, below damage center 4, more damage would be caused by the storm flood at river stages of fourteen (14) to seventeen (17) feet than by the additional flow of dam failures with about four to five feet additional depth. It is estimated that five additional homes or business buildings would be damaged by the addition of dam failure flow. Dam failure effects below the confluence with the Westfield River would probably not be significant.

This analysis is summarized in the following table.

# DOWNSTREAM IMPACTS OF DAM FAILURE

			Before Dam Failure				After Dam Failure				
Map Location No.	From Dam Feet	Feature	No. of dwellings (Buildings)	Flood Stage cfs-ft.	Depth Over Rd. Ft.	Buildings Damaged	Flood Stage cfs-ft.	Depth Over Road feet	Bldg. Damaged Feet	Comments	
0	0	Dam	0	750 7.0		0	7,515 11		0		
1	600	Bonny Rigg Hill Rd.	0	750 7.0	0.7	0	7,310 11	2.0	0	Rd. wash out if dam fails	
2	7,000	Rt. 20 over Spark Brk	0	1,464 3.0	0.2	0	7,815 5.9	2.5	0	Rd. wash out if dam fails	
3	10,000	Rt. 20 over Walker Brk	0	8,144 13.7	1.3	0	14,350 18.4	4.9	0	Rd. wash out if dam fails	
4	13,000	Rt. 20 over Walker Brk	1	8,144 13.7	2.1	0	14,120 18.2	4.2	0	Rd. wash out from storm	
5	16,000	Rt. 20 over Walker Brk	1	11,375 16.4	6.7	1	17,150 20.0	8.8	1	Rd. wash out; hse wash out from storm	
6	19,000	Blandford Rd. over Walker Brook	2	12,480 17.1	1.5	1	18,060 21.1	5.2	2	Rd & hse. wash out from storm; 2nd hse wash out if dam fails	
7	22,000	Walker Island Campground	50 seasonal 1 perm.	13,050 6.9	2.9	50 1	18,420 7.8	3.8	50 1	Rd. & camp wash out from storm	
8	25,000	Town Rd. over Walker Brk	4	14,030 9.5	1.7	2	19,300 11.2	5.2	2	Rd. & 2 hses wash out by storm	
9	38,000	Rt. 20 over Walker Brk	15	14,030 9.6	2.7	8	18,710 11.0	4.4	12	Rd & Hse wash out by storm; 4 additional houses wash out if dam fails	
9	38,500	Town St. over Westfield Rvr	50	35,300 13.5	0	0	40,000 14.2	0	0	Area is safe	



- SCALE -  
1000' 0' 1000' 2000' 3000' 4000'

FROM USGS OTIS  
BECKET  
CHESTER

DRAINAGE AREA

DAMAGE CENTER

SWAMPS



①



TIGHE B BOND / SCI  
CONSULTING ENGINEERS  
EASTHAMPTON, MASS.

U.S. ARMY ENGINEER DIV. NEW ENGLAND  
CORPS OF ENGINEERS  
WALTHAM, MASS.

# NATIONAL PROGRAM OF INSPECTION OF NON-FED. DAMS LOCATION AND DOWNSTREAM HAZARD MAP

INDIAN LAKE DAM (MA01051)  
BERKSHIRE COUNTY

BECKET  
MASSACHUSETTS

SCALE: AS NOTED

DATE: DECEMBER 1979

## SECTION 6 - EVALUATION OF STRUCTURAL STABILITY

### 6.1 Visual Observations

Visual inspection revealed no signs of significant displacement of the embankment or structures. The southeast spillway wall shows signs of a cold joint during concrete placement. Seepage and efflorescence along this line indicates that active deterioration is underway which might result in a hazardous condition in the future.

### 6.2 Design and Construction Data

A review of the construction plans indicates that the structures were designed in accordance with standard engineering practice. A review of the construction notes indicates that the embankment was constructed in accordance with standard engineering practice as far as it progressed.

### 6.3 Post Construction Changes

The Massachusetts Division of Waterways inspection report for October 20, 1977 indicates that flashboards were in place to elev. 1478 which is about 1 foot above the maximum design pond elevation. Some flashboards were subsequently removed. At the time of this inspection, flashboards were about 1.4 feet above the concrete spillway crest (elev. 1474.4 MSL).

The October, 1977 inspection reported a wet area about 8 feet from the top of the dam left of the spillway and seepage of about 1 gpm at a point about 2 feet up from toe about 25 feet left of the spillway. This was not noted at this inspection.

### 6.4 Seismic Stability

The dam is located in seismic zone No. 2. According to the recommended Corps of Engineers Guidelines, a seismic analysis is not warranted.

## SECTION 7 - ASSESSMENT, RECOMMENDATIONS AND REMEDIAL MEASURES

### 7.1 Dam Assessment

#### (a) Condition

The dam is generally in fair condition. The embankment and spillway are stable. The embankment has not been completed to design height, the downstream slopes are not protected and the left foundation drain is not operating properly. There are signs of leakage through and under the left embankment. The spillway bridge for access to the stop log facilities and the fence at the spillway wing walls have not been installed. The cold concrete joint could eventually be a hazard.

#### (b) Adequacy of Information

There is sufficient design and construction data to permit an assessment of dam safety when combined with visual inspection, past performance, and sound engineering judgment.

#### (c) Urgency

The recommendations and remedial measures described herein should be implemented within one year of receipt of this Phase I Inspection Report.

### 7.2 Recommendations

The recommendations of this Phase 1 investigation are that the following additional studies or modifications be made under the supervision of a registered professional engineer:

1. Complete embankment to full design height
2. Provide downstream slope protection, preferably with riprap stone, that will discourage motorcycle trespass and reduce the rate of erosion.
3. Modify the stop log guides so that thick flashboards cannot be installed and the guide height is limited to a safe elevation.
4. Replace existing stop log with flashboards of appropriate thickness to allow washout during floods.
5. Install spillway bridge to facilitate flashboard operation.
6. Grout or seal the concrete cold joint to prevent further deterioration of concrete and reinforcing steel.
7. Excavate at a number of locations along the left foundation toe drain to determine the cause of the malfunction of this drain; implement appropriate corrective measures once the source of the malfunction is determined.

### 7.3 Remedial Measures

The following remedial operation and maintenance procedures are recommended:

1. Immediately remove all stop logs or flashboards from spillway and keep them removed and away from the dam site until all recommendations and remedial measures have been completed.
2. Develop a downstream emergency flood response and warning system.
3. Develop a program of annual technical inspections.
4. Develop a program of regular monthly operation and maintenance inspections.
5. Establish a monitoring procedure and program at the dam during and just after periods of intense rainfall or flooding.
6. Repair sluice gate lift stand and mount.

### 7.4 Alternatives

There are no meaningful alternatives to the above recommendations except as follows:

1. Recommendation 7.2-3 - In lieu of modifying the stop log guides, they should be removed or blocked to prevent installation of any stop logs.
2. The dam may be drained by removing the sluice gate and breaching the embankment to a width of at least 25 feet and a height near the bottom of the reservoir.

APPENDIX A  
INSPECTION CHECKLIST



PARTY ORGANIZATION:

DATE 10/31/79

WEATHER Clear, calm, fair-50°F

W.S. ELEV. 1474.4 U.S. 1466<sup>+</sup> D.N.S.  
Based on design elevation of  
structures

PARTY:

- |  |           |
|--|-----------|
| 1. <u>J.W. Powers , P.E. Project Manager</u>               | 6. _____  |
| 2. <u>G.H. McDonnell , P.E., Hydrology/<br/>Hydraulics</u> | 7. _____  |
| 3. <u>E.A. Moe , P.E., Soils/Hydraulics</u>                | 8. _____  |
| 4. <u>H.A. Koski , Civil</u>                               | 9. _____  |
| 5. <u>O.H. Dumais , Civil</u>                              | 10. _____ |

REMARKS

1. All project features were inspected by all party members.
- 2.
- 3.
- 4.
- 5.
- 6.
- 7.
- 8.
- 9.
- 10.

## INSPECTION CHECK LIST

PROJECT Indian Lake DamDATE 10/31/79PROJECT FEATURE EmbankmentNAME Tighe & Bond party

DISCIPLINE \_\_\_\_\_

NAME \_\_\_\_\_

AREA EVALUATED	CONDITIONS
<u>DAM EMBANKMENT</u>	
Crest Elevation	- SE end: 1.1' lower than conc. wall, to 117' out. NW end: 1.05' lower than conc. wall to 52' out, where it is 0.3'+ low, to grade 168' out
Current Pool Elevation	- 1.45' above concrete crest
Maximum Impoundment to Date	- Water mark 1.1' below top of conc. wing wall. Tail water maximum 11.6' below top of concrete wing wall
Surface Cracks	- No surface cracks evident
Pavement Condition	- No pavement
Movement or Settlement of Crest	- Center is 1.1' low both sides of spillway. Probably constructed low not settlement.
Lateral Movement	- None evident
Vertical Alignment	- 1.1' low at spillway - see above
Horizontal Alignment	- Approximately as plans show
Condition at Abutment and at Concrete Structures	- 1.1' low see above
Indications of Movement of Structural Items on Slopes	- None
Trespassing on Slopes	- Motorcycle tracks on downstream & top.
Vegetation on Slopes	- None except on loam piles that have not been spread
Sloughing or Erosion of Slopes or Abutments	- Minor rain rills in downstream gravelly slope
Rock Slope Protection - Riprap Failures	- None evident
Unusual Movement or Cracking at or near Toes	- None evident
Unusual Embankment or Downstream Seepage	- None
Piping or Boils	- None
Foundation Drainage Features	- #1 toe drain had been plugged. Flowed freely - no sand or grit. 1/2"x6"x1 fps 1000 cfs. Pipe offset at joint: 1/2"
Toe Drains	- low in bank.
Instrumentation System	- #2 toe drain dry. Offset at joint 3/4" low in embankment should be checked.
	- None

## INSPECTION CHECK LIST

PROJECT Indian Lake DamDATE 10/31/79

PROJECT FEATURE \_\_\_\_\_

NAME Tighe & Bond party

DISCIPLINE \_\_\_\_\_

NAME \_\_\_\_\_

AREA EVALUATED	CONDITION
<u>OUTLET WORKS - INTAKE CHANNEL AND</u> <u>INTAKE STRUCTURE</u>	
a. Approach Channel	Submerged
Slope Conditions	Good
Bottom Conditions	Submerged, not visible due to turbidity
Rock Slides or Falls	None
Log Boom	None
Debris	None
Condition of Concrete Lining	Good, except south wing wall shows cold pour joint in concrete. Reinforcing steel & tie wire protruded from top of wing wall back-up
Drains or Weep Holes	None visible
b. Intake Structure	Gate & thimble submerged and not visible
Condition of Concrete	Good
Stop Logs and Slots	Good, top 1.45' above concrete crest. 3/4" water over top of stop logs.

## INSPECTION CHECK LIST

PROJECT Indian Lake DamDATE 10/31/79

PROJECT FEATURE \_\_\_\_\_

NAME Tighe & Bond party

DISCIPLINE \_\_\_\_\_

NAME \_\_\_\_\_

AREA EVALUATED	CONDITION
<u>OUTLET WORKS - CONTROL TOWER</u>	
a. Concrete and Structural	
General Condition	West wall good. East wall shows cold joint in concrete pour near mid height.
Condition of Joints	Satisfactory, only minor shifting evident
Spalling	None
Visible Reinforcing	None
Rusting or Staining of Concrete	Rusty re. steel & tie wire protrudes above south wing wall back up block.
Any Seepage or Efflorescence	On SE wall. Seepage & efflorescence is higher near embankment center than at downstream toe. 1' above tail water at toe. 3'-4' near center of stilling basin
Joint Alignment	
Unusual Seepage or Leaks in Gate Chamber	None visible. Gate was submerged.
Cracks	Minor cold joint cracks in SE wall
Rusting or Corrosion of Steel	No fence or cat walk. Fence post sockets are rusting
b. Mechanical and Electrical	
Air Vents	None
Float Wells	None
Crane Hoist	None
Elevator	None
Hydraulic System	None
Service Gates	Rodney Hunt 43941-2/S-5002-A one base bolt on stand missing
Emergency Gates	Stop logs
Lightning Protection System	None
Emergency Power System	None
Wiring and Lighting System in Gate Chamber	None

## INSPECTION CHECK LIST

PROJECT Indian Lake DamDATE 10/31/79

PROJECT FEATURE \_\_\_\_\_

NAME Tighe & Bond party

DISCIPLINE \_\_\_\_\_

NAME \_\_\_\_\_

AREA EVALUATED	CONDITION
<u>OUTLET WORKS - TRANSITION AND CONDUIT</u>	NONE
General Condition of Concrete	See other pages
Rust or Staining on Concrete	
Spalling	
Erosion or Cavitation	
Cracking	
Alignment of Monoliths	
Alignment of Joints	
Numbering of Monoliths	

## INSPECTION CHECK LIST

PROJECT Indian LakeDATE 10/31/79

PROJECT FEATURE \_\_\_\_\_

NAME Tighe & Bond party

DISCIPLINE \_\_\_\_\_

NAME \_\_\_\_\_

AREA EVALUATED	CONDITION
<u>OUTLET WORKS - OUTLET STRUCTURE AND OUTLET CHANNEL</u>	
General Condition of Concrete	
Rust or Staining	Good
Spalling	None
Erosion or Cavitation	None
Visible Reinforcing	None
Any Seepage or Efflorescence	None
Condition at Joints	Satisfactory joint open $\leq 1/8"$
Drain holes	None
Channel	Riprap
Loose Rock or Trees Overhanging Channel	None
Condition of Discharge Channel	Good

# INSPECTION CHECK LIST

PROJECT Indian Lake Dam

DATE 10/31/79

PROJECT FEATURE \_\_\_\_\_

NAME Tighe & Bond party

DISCIPLINE \_\_\_\_\_

NAME \_\_\_\_\_

AREA EVALUATED	CONDITION
<u>OUTLET WORKS - SPILLWAY WEIR, APPROACH AND DISCHARGE CHANNELS</u>	
a. Approach Channel	Submerged
General Condition	Features above water are in good condition
Loose Rock Overhanging Channel	None
Trees Overhanging Channel	None
Floor of Approach Channel	Submerged
b. Weir and Training Walls	
General Condition of Concrete	Good except seepage and efflorescence
Rust or Staining	None
Spalling	
Any Visible Reinforcing	None
Any Seepage or Efflorescence	SW wing wall & channel wall has seepage & efflorescence 1' above tail water near end & 3'-4' above tail water at dam $\frac{1}{2}$
Drain Holes	None
c. Discharge Channel	
General Condition	Good
Loose Rock Overhanging Channel	None
Trees Overhanging Channel	
Floor of Channel	Riprap    Transition to curve
Other Obstructions	

## INSPECTION CHECK LIST

PROJECT Indian Lake DamDATE 10/31/79

PROJECT FEATURE \_\_\_\_\_

NAME Tighe & Bond/SCI

DISCIPLINE \_\_\_\_\_

NAME \_\_\_\_\_

AREA EVALUATED	CONDITION
<u>OUTLET WORKS - SERVICE BRIDGE</u>	
a. Super Structure	None in place
Bearings	
Anchor Bolts	
Bridge Seat	
Longitudinal Members	
Under Side of Deck	
Secondary Bracing	
Deck	
Drainage System	
Railings	None. Pipe sockets rusting rapidly
Expansion Joints	
Paint	
b. Abutment & Piers	
General Condition of Concrete	
Alignment of Abutment	
Approach to Bridge	
Condition of Seat & Backwall	



APPENDIX B  
ENGINEERING DATA

Design and construction information is located at the following places.


<u>Item</u>	<u>Location</u>
Design data	Barnes & Jarvis, Inc., 61 Batterymarch St., Boston, Mass.
Earthwork design	Haley & Aldrich, Inc., 238 Main St. Cambridge, Mass.
Construction records	Haley & Aldrich, Inc.
As-built plans	Mr. John Hannon, Mass. DEQE, Waterways Division, 100 Nashua St., Boston, Mass. 02114
Inspection Reports	Mr. John Hannon, Mass. DEQE, Waterways Division

Copies of sheets 2, 3, 4, and 5 of as-built plans are attached hereafter.

A copy of the Massachusetts Division of Waterways inspection report is attached hereafter.


BORI

Sheet No. 101




NOTE: THE LAYER 10-12-13 IS NOT SHOWN IN THE CROSS SECTION  
NOTE: LAYER 10-12-13 IS NOT SHOWN IN THE CROSS SECTION  
NOTE: LAYER 10-12-13 IS NOT SHOWN IN THE CROSS SECTION

Sheet No. 101A




NOTE: THE LAYER 10-12-13 IS NOT SHOWN IN THE CROSS SECTION  
NOTE: LAYER 10-12-13 IS NOT SHOWN IN THE CROSS SECTION  
NOTE: LAYER 10-12-13 IS NOT SHOWN IN THE CROSS SECTION

Sheet No. 102



NOTE: THE LAYER 10-12-13 IS NOT SHOWN IN THE CROSS SECTION  
NOTE: LAYER 10-12-13 IS NOT SHOWN IN THE CROSS SECTION  
NOTE: LAYER 10-12-13 IS NOT SHOWN IN THE CROSS SECTION

Sheet No. 103







NOTE: THE LAYER 10-12-13 IS NOT SHOWN IN THE CROSS SECTION  
NOTE: LAYER 10-12-13 IS NOT SHOWN IN THE CROSS SECTION  
NOTE: LAYER 10-12-13 IS NOT SHOWN IN THE CROSS SECTION

TE

TEST PIT REPORT		TEST PIT NO. 1
PROJECT: PROPOSED DAM SITE, BECKETT, MASS.		DATE: 3/27/70
CLIENT: BARNES & JONES, INC., BOSTON, MASS.		DATE: 3/27/70
CONTRACTOR: AMERICAN CONSTRUCTION CO., BECKETT, MASS.		DATE: 3/27/70
EQUIPMENT USED: 1. 2500 BOLLING, 2. 3. 4. 5. 6. 7. 8. 9. 10. 11. 12. 13. 14. 15. 16. 17. 18. 19. 20. 21. 22. 23. 24. 25. 26. 27. 28. 29. 30. 31. 32. 33. 34. 35. 36. 37. 38. 39. 40. 41. 42. 43. 44. 45. 46. 47. 48. 49. 50. 51. 52. 53. 54. 55. 56. 57. 58. 59. 60. 61. 62. 63. 64. 65. 66. 67. 68. 69. 70. 71. 72. 73. 74. 75. 76. 77. 78. 79. 80. 81. 82. 83. 84. 85. 86. 87. 88. 89. 90. 91. 92. 93. 94. 95. 96. 97. 98. 99. 100.		DATE: 3/27/70
DESCRIPTION OF MATERIALS		REMARKS
0.0 - 1.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
1.0 - 2.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
2.0 - 3.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
3.0 - 4.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
4.0 - 5.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
5.0 - 6.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
6.0 - 7.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
7.0 - 8.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
8.0 - 9.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
9.0 - 10.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
10.0 - 11.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
11.0 - 12.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
12.0 - 13.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
13.0 - 14.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
14.0 - 15.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
15.0 - 16.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
16.0 - 17.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
17.0 - 18.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
18.0 - 19.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
19.0 - 20.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
20.0 - 21.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
21.0 - 22.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
22.0 - 23.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
23.0 - 24.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
24.0 - 25.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
25.0 - 26.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
26.0 - 27.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
27.0 - 28.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
28.0 - 29.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
29.0 - 30.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
30.0 - 31.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
31.0 - 32.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
32.0 - 33.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
33.0 - 34.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
34.0 - 35.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
35.0 - 36.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
36.0 - 37.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
37.0 - 38.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
38.0 - 39.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
39.0 - 40.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
40.0 - 41.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
41.0 - 42.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
42.0 - 43.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
43.0 - 44.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
44.0 - 45.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
45.0 - 46.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
46.0 - 47.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
47.0 - 48.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
48.0 - 49.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
49.0 - 50.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
50.0 - 51.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
51.0 - 52.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
52.0 - 53.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
53.0 - 54.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
54.0 - 55.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
55.0 - 56.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
56.0 - 57.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
57.0 - 58.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
58.0 - 59.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
59.0 - 60.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
60.0 - 61.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
61.0 - 62.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
62.0 - 63.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
63.0 - 64.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
64.0 - 65.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
65.0 - 66.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
66.0 - 67.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
67.0 - 68.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
68.0 - 69.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
69.0 - 70.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
70.0 - 71.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
71.0 - 72.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
72.0 - 73.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
73.0 - 74.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
74.0 - 75.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
75.0 - 76.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
76.0 - 77.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
77.0 - 78.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
78.0 - 79.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
79.0 - 80.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
80.0 - 81.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
81.0 - 82.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
82.0 - 83.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
83.0 - 84.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
84.0 - 85.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
85.0 - 86.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13
86.0 - 87.0	CLAYEY SILT, 10-12-13	CLAYEY SILT, 10-12-13

# BORING LOGS



## TEST PITS

TEST PIT NO.	DATE	LOCATION	DEPTH (ft)	SOIL DESCRIPTION	WATER LEVEL (ft)
1	1974	...	...	...	...
2	1974	...	...	...	...
3	1974	...	...	...	...
4	1974	...	...	...	...
5	1974	...	...	...	...
6	1974	...	...	...	...
7	1974	...	...	...	...
8	1974	...	...	...	...
9	1974	...	...	...	...
10	1974	...	...	...	...

TEST PIT NO.	DATE	LOCATION	DEPTH (ft)	SOIL DESCRIPTION	WATER LEVEL (ft)
1	1974	...	...	...	...
2	1974	...	...	...	...
3	1974	...	...	...	...
4	1974	...	...	...	...
5	1974	...	...	...	...
6	1974	...	...	...	...
7	1974	...	...	...	...
8	1974	...	...	...	...
9	1974	...	...	...	...
10	1974	...	...	...	...

TEST PIT NO.	DATE	LOCATION	DEPTH (ft)	SOIL DESCRIPTION	WATER LEVEL (ft)
1	1974	...	...	...	...
2	1974	...	...	...	...
3	1974	...	...	...	...
4	1974	...	...	...	...
5	1974	...	...	...	...
6	1974	...	...	...	...
7	1974	...	...	...	...
8	1974	...	...	...	...
9	1974	...	...	...	...
10	1974	...	...	...	...



TEST PIT NO.	DATE	LOCATION	DEPTH (ft)	SOIL DESCRIPTION	WATER LEVEL (ft)
1	1974	...	...	...	...
2	1974	...	...	...	...
3	1974	...	...	...	...
4	1974	...	...	...	...
5	1974	...	...	...	...
6	1974	...	...	...	...
7	1974	...	...	...	...
8	1974	...	...	...	...
9	1974	...	...	...	...
10	1974	...	...	...	...


### GENERAL AND TEST PIT NOTES

1. Location of borings and test pits are shown on Sheet No. 4.
2. Borings were taken on June 19, 21, & 23, 1974 by Richard Dillman and Bruce Coy, Inc., Braintree, Mass.
3. Water reading on boring logs is taken at a point in water column of boring - usually between 1 and 2 ft.
4. Features in boring logs are shown by asterisk (\*) and by the word "feature" in the soil description. In water level logs, the word "feature" is used as well as the word "level".
5. Test pit boring log is shown as a line graph.


Copy available to DTIC does not permit fully legible reproduction

INDIAN LAKE DEVELOPMENT BORINGS LOGS		JOB NO. <b>73-260</b> SCA 1
RICHARD A. JARVIS ENGINEER 100 BENTLEY STREET, BOSTON, MASS. 02111 GEORGE S. ALLEN & ASSOCIATES, INC. Local Surveyors South Shore Road WILMINGTON, MASS. Consulting Soil Engineers Cambridge		DATE 8/1/74 BY CAD: L.G.W. SHEET NO. <b>2</b>







TYPICAL SECTION  
DIVERSION CHANNEL



TYPICAL DAM SECTION 'A'



TYPICAL DAM SECTION 'B'



1. LAYING OUT THE DIVERSION CHANNEL

1. Lay out the diversion channel with rubble and boulders at 10% slope to meet, size which can be removed within the channel lining layer.
2. After completion of constructing the Billing, the spillway structure and installing the Drain, redirect stream into principal spillway.
3. Lay out the diversion channel lining and all other work within the channel excavation within the diversion area and flatten channel side slopes to 4:1 ratio to 1:1 ratio.
4. Partially excavate with gabionment material following the plan of the spillway.

1490  
1480  
1470  
1460  
1450  
1440  
1430

1490  
1480  
1470  
1460  
1450  
1440  
1430

TYPICAL CROSS SECTION FOR DAM

MATERIAL	DESCRIPTION
(1)	Gravel Bottom
(11)	Impervious Bottom
(11a)	Impervious Bottom
(11b)	Granular Bottom
(IV)	App. Key

On site clean sandy gravel or coarse sand to be used to compact the dam foundation. These part will be provided below approximately 10' and 12' must be placed "fourth-way".

Clasical till containing a mixture of silt and clay obtained from study of the area. Placed and supported in layers for a purpose cut-off.

Identical to 11. Placed under the compacted at surface.


On site sand, gravel, boulders, generally used. Placed and supported in layers.

Dumped with fill having a minimum of 10' by weight pressure, 10' by weight, size 10'.

Copy available to DTIC does not permit fully legible reproduction




INDIAN LAKE DEVELOPMENT		JOB NO.
SECRET		734260
OUTLET STREAM DAM SECTIONS & PLAN		DATE OF ISSUE
DRAWN BY		DATE OF ISSUE
CHECKED BY		DATE OF ISSUE
APPROVED BY		DATE OF ISSUE
SHEET NO.		3



Sheet 11

1082




Copy available to DTIC does not permit fully legible reproduction

INDIAN LAKE DEVELOPMENT		JOB NO.
PROJECT		73-260
DAM SITE PLAN		SCALE
DANIEL & JORDAN		AS NOTED
ALBANY, NEW YORK		
WILLIAM S. JORDAN & ASSOCIATES, INC.		
Civil Engineers		
JAMES S. JORDAN, INC.		
Consulting Civil Engineers		
ALBANY, NEW YORK		



2082





PLAN

1. The spillway shall be constructed of concrete or steel, and shall be capable of withstanding the full design flood without any damage to the structure or to the spillway gates.

2. The spillway shall be capable of withstanding the full design flood without any damage to the structure or to the spillway gates.

3. The spillway shall be capable of withstanding the full design flood without any damage to the structure or to the spillway gates.

4. The spillway shall be capable of withstanding the full design flood without any damage to the structure or to the spillway gates.

5. The spillway shall be capable of withstanding the full design flood without any damage to the structure or to the spillway gates.

6. The spillway shall be capable of withstanding the full design flood without any damage to the structure or to the spillway gates.

7. The spillway shall be capable of withstanding the full design flood without any damage to the structure or to the spillway gates.

8. The spillway shall be capable of withstanding the full design flood without any damage to the structure or to the spillway gates.

9. The spillway shall be capable of withstanding the full design flood without any damage to the structure or to the spillway gates.

10. The spillway shall be capable of withstanding the full design flood without any damage to the structure or to the spillway gates.

11. The spillway shall be capable of withstanding the full design flood without any damage to the structure or to the spillway gates.

12. The spillway shall be capable of withstanding the full design flood without any damage to the structure or to the spillway gates.

RAILING POST

TOP OF STRUCTURE

EL 1075 MAXIMUM W.L.

EL 1075 NORMAL W.L.

EL 1073 MINIMUM W.L.

RECESS FOR FLASHBOARDS

EL 1075

STOP LINE

EL 1073

CONCRETE BULKHEAD UPPIERS

SLIDING GATE

EL 1071

EL 1072

EL 1073

EL 1074

EL 1075

EL 1076

EL 1077

EL 1078

EL 1079

EL 1080

EL 1081

EL 1082

EL 1083

EL 1084

EL 1085

EL 1086

EL 1087

EL 1088

EL 1089

EL 1090

EL 1091

EL 1092

EL 1093

EL 1094

EL 1095

EL 1096

EL 1097

EL 1098

EL 1099

EL 1100

EL 1101

EL 1102

EL 1103

EL 1104

EL 1105

EL 1106

EL 1107

EL 1108

EL 1109

EL 1110

EL 1111

EL 1112

EL 1113

EL 1114

EL 1115

EL 1116

EL 1117

EL 1118

EL 1119

EL 1120

EL 1121

EL 1122

EL 1123

EL 1124

EL 1125

EL 1126

EL 1127

EL 1128

EL 1129

EL 1130

EL 1131

EL 1132

EL 1133

EL 1134

EL 1135

EL 1136

EL 1137

EL 1138

EL 1139

EL 1140

EL 1141

EL 1142

EL 1143

EL 1144

EL 1145

EL 1146

EL 1147

EL 1148

EL 1149

EL 1150

EL 1151

EL 1152

EL 1153

EL 1154

EL 1155

EL 1156

EL 1157

EL 1158

EL 1159

EL 1160

EL 1161

EL 1162

EL 1163

EL 1164

EL 1165

EL 1166

EL 1167

EL 1168

EL 1169

EL 1170

EL 1171

EL 1172

EL 1173

EL 1174

EL 1175

EL 1176

EL 1177

EL 1178

EL 1179

EL 1180

EL 1181

EL 1182

EL 1183

EL 1184

EL 1185

EL 1186

EL 1187

EL 1188

EL 1189

EL 1190

EL 1191

EL 1192

EL 1193

EL 1194

EL 1195

EL 1196

EL 1197

EL 1198

EL 1199

EL 1200

EL 1201

EL 1202

EL 1203

EL 1204

EL 1205

EL 1206

EL 1207

EL 1208

EL 1209

EL 1210

EL 1211

EL 1212

EL 1213

EL 1214

EL 1215

EL 1216

EL 1217

EL 1218

EL 1219

EL 1220

EL 1221

EL 1222

EL 1223

EL 1224

EL 1225

EL 1226

EL 1227

EL 1228

EL 1229

EL 1230

EL 1231

EL 1232

EL 1233

EL 1234

EL 1235

EL 1236

EL 1237

EL 1238

EL 1239

EL 1240

EL 1241

EL 1242

EL 1243

EL 1244

EL 1245

EL 1246

EL 1247

EL 1248

EL 1249

EL 1250

EL 1251

EL 1252

EL 1253

EL 1254

EL 1255

EL 1256

EL 1257

EL 1258

EL 1259

EL 1260

EL 1261

EL 1262

EL 1263

EL 1264

EL 1265

EL 1266

EL 1267

EL 1268

EL 1269

EL 1270

EL 1271

EL 1272

EL 1273

EL 1274

EL 1275

EL 1276

EL 1277

EL 1278

EL 1279

EL 1280

EL 1281

EL 1282

EL 1283

EL 1284

EL 1285

EL 1286

EL 1287

EL 1288

EL 1289

EL 1290

EL 1291

EL 1292

EL 1293

EL 1294

EL 1295

EL 1296

EL 1297

EL 1298

EL 1299

EL 1300

EL 1301

EL 1302

EL 1303

EL 1304

EL 1305

EL 1306

EL 1307

EL 1308

EL 1309

EL 1310

EL 1311

EL 1312

EL 1313

EL 1314

EL 1315

EL 1316

EL 1317

EL 1318

EL 1319

EL 1320

EL 1321

EL 1322

EL 1323

EL 1324

EL 1325

EL 1326

EL 1327

EL 1328

EL 1329

EL 1330

EL 1331

EL 1332

EL 1333

EL 1334

EL 1335

EL 1336

EL 1337

EL 1338

EL 1339

EL 1340

EL 1341

EL 1342

EL 1343

EL 1344

EL 1345

EL 1346

EL 1347

EL 1348

EL 1349

EL 1350

EL 1351

EL 1352

EL 1353

EL 1354

EL 1355

EL 1356

EL 1357

EL 1358

EL 1359

EL 1360

EL 1361

EL 1362

EL 1363

EL 1364

EL 1365

EL 1366

EL 1367

EL 1368

EL 1369

EL 1370

EL 1371

EL 1372

EL 1373

EL 1374

EL 1375

EL 1376

EL 1377

EL 1378

EL 1379

EL 1380

EL 1381

EL 1382

EL 1383

EL 1384

EL 1385

DATE: 11/2/79

[illegible]

## INSPECTION REPORT - DAMS AND RESERVOIRS

1. Location: City/Town BECKET Dam No. 1-2-22-17Name of Dam Indian Lake Inspected by RJJordan-RSpaniolDate of Inspection October 20, 1977

Previous Inspection \_\_\_\_\_

2. Owner/s per: Assessors \_\_\_\_\_  
Reg. of Deeds \_\_\_\_\_ Personal Contact \_\_\_\_\_1. J. F. Hansman Indian Lake Estates Becket, MA  
Name \_\_\_\_\_ St. & No. \_\_\_\_\_ City/Town/State \_\_\_\_\_ Tel. No. \_\_\_\_\_2. \_\_\_\_\_  
Name \_\_\_\_\_ St. & No. \_\_\_\_\_ City/Town/State \_\_\_\_\_ Tel. No. \_\_\_\_\_

3. Caretaker (if any) e.g. superintendent, plant manager, appointed by absentee owner, appointed by multi owners.

Name \_\_\_\_\_ St. &amp; No. \_\_\_\_\_ City/Town/State \_\_\_\_\_ Tel. No. \_\_\_\_\_

4. No. of Pictures taken \_\_\_\_\_

5. Degree of Hazard: (If dam should fail completely)\*

1. Minor X 2. Moderate \_\_\_\_\_

3. Severe \_\_\_\_\_ 4. Disastrous \_\_\_\_\_

\*This rating may change as land use changes (future development)

6. Outlet Control: Automatic \_\_\_\_\_ Manual X  
Operative X Yes \_\_\_\_\_ No \_\_\_\_\_Comments: \_\_\_\_\_  
\_\_\_\_\_

7. Upstream Face of Dam:

Condition: 1. Good X 2. Minor Repairs \_\_\_\_\_

3. Major Repairs \_\_\_\_\_ 4. Urgent Repairs \_\_\_\_\_

Comments: \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

## 8. Downstream Face of Dam:

Condition: 1. Good \_\_\_\_\_ 2. Minor Repairs X \_\_\_\_\_  
3. Major Repairs \_\_\_\_\_ 4. Urgent Repairs \_\_\_\_\_

## 9. Emergency Spillway

Condition: 1. Good \_\_\_\_\_ 2. Minor Repairs \_\_\_\_\_  
3. Major Repairs \_\_\_\_\_ 4. Urgent Repairs \_\_\_\_\_

Comments: \_\_\_\_\_  
\_\_\_\_\_

10. Water level at time of inspection 0.4 above X below \_\_\_\_\_  
top of dam \_\_\_\_\_  
principal spillway \_\_\_\_\_  
other Splashboards

## 11. Summary of Deficiencies Noted:

\_\_\_\_\_ Growth (Trees & Brush) on Embankment \_\_\_\_\_  
\_\_\_\_\_ Animal Burrows and Washouts \_\_\_\_\_  
\_\_\_\_\_ Damage to slopes or top of dam \_\_\_\_\_  
\_\_\_\_\_ Cracked or damaged masonry \_\_\_\_\_  
X Evidence of seepage \_\_\_\_\_  
\_\_\_\_\_ Evidence of piping \_\_\_\_\_  
X Erosion \_\_\_\_\_  
X Leaks \_\_\_\_\_  
\_\_\_\_\_ Trash and/or debris impeding flow \_\_\_\_\_  
\_\_\_\_\_ Clogged or blocked spillway \_\_\_\_\_  
\_\_\_\_\_ Other \_\_\_\_\_

- 3 -

12. Remarks & Recommendations; (Fully Explain)  
PREVIOUS INSPECTION DATE: NEW STRUCTURE

This new structure has not been completed. The downstream slope and top of embankment have not been seeded and due to the lack of turf cover, small areas of minor erosion have developed.

The chain link fence and spillway catwalk have not been installed. Without the catwalk, the installation and removal of the flashboards is difficult and hazardous. This work was to have been completed in early 1976.

On this date, the pond elevation was extremely high. The flashboards in place exceed the maximum design pond elevation by approximately one foot, and five inches of water was flowing over the boards. Settlement has occurred at both sides of the spillway and the dam is within one foot of topping.

On the left side of the spillway, approximately eight feet from the top of the dam we found a very soft wet area approximately three feet in diameter. Although no flow was observed, this condition should be investigated.

Approximately 25' from the left abutment, two feet up from the toe, a flow of approximately 1 GPM was found. It appears to be coming from the embankment, however, it could be a spring caused by the high water table. This condition also warrants investigation.

Foreclosure proceedings are in progress, and the owner is unavailable. The Community Savings Bank of Springfield is handling the foreclosure, and will soon be the owners of the dam and surrounding property. I spoke with Mr. Guyette, a vice-president of the bank, and expressed my concern with the safety of the structure and advised him to lower the pond by several feet as soon as possible.

With his permission, I contacted the Becket Board of Selectmen and requested them to open the gate and remove the stop logs. To date 8" of boards have been removed, and a total of three feet of boards will be removed over a period of time to safely lower the pond.


For location see Topo Sheet 5-D and 6-B.

## 13. Overall Condition:

- \_\_\_\_\_ 1. Safe \_\_\_\_\_
- \_\_\_\_\_ 2. Minor repairs needed \_\_\_\_\_
- \_\_\_\_\_ 3. Conditionally safe - major repairs needed \_\_\_\_\_
- \_\_\_\_\_ 4. Unsafe \_\_\_\_\_
- \_\_\_\_\_ 5. Reservoir impoundment no longer exists (explain)

Recommend removal from inspection list \_\_\_\_\_

APPENDIX C  
PHOTOGRAPHS



- ➡ AERIAL OVERVIEW
- ▷ APPENDIX C

TIGHE & BOND / SCI CONSULTING ENGINEERS EASTHAMPTON, MASS.		U.S. ARMY ENGINEER DIV. NEW ENGLAND CORPS OF ENGINEERS WALTHAM, MASS.	
NATIONAL PROGRAM OF INSPECTION OF NON-FED. DAMS			
LOCATION AND ORIENTATION OF PHOTOS			
INDIAN LAKE DAM (MA01051)		BECKET	
BERKSHIRE COUNTY		MASSACHUSETTS	
		SCALE: 1" = 100'	
		DATE: DECEMBER 1979	



PHOTO 1

Looking northwesterly at  
face of dam




PHOTO 2



Looking west downstream  
slope west end of dam



PHOTO 3

Looking southwesterly at  
downstream face southeast  
end of dam





View of spillway wing  
looking west, left founda-  
tion drain



PHOTO 7

Right foundation drain  
just after clearing sand  
plug



PHOTO 8

Right foundation drain  
about 30 minutes after  
clearing sand plug

PLATE 9

Looking southwesterly at  
spillway plunge pool




PLATE 10

Looking southerly at south-  
east spillway wall showing  
a joint, leakage and  
efflorescence






PHOTO 11

Looking southeasterly at  
water and wet area at left  
toe of dam



PHOTO 12

Looking north toward Benny  
Rigg Hill Road across swamp  
and outlet brook

PHOTO 13  
Looking east at  
the spillway inlet





PHOTO 14

Looking west at piers  
and west spillway inlet  
wing wall



APPENDIX D  
HYDROLOGIC AND HYDRAULIC  
COMPUTATIONS

HYDRAULIC COMPUTATIONS

LOCATION

DRAINAGE AREA

DAM SIZE

DISCHARGE CAPACITY

RESERVOIR CAPACITY

0-19-24  
11/5/79  
Moe.  
chk'd DML

## Indian Lake Dam

Location: N  $42^{\circ} 14' 57''$   
W  $73^{\circ} 01' 27''$

Elevation: normal pool = 1475.0 MSL

From project plans

confirmed by U.S.G.S. topo sheet

U.S. G.S. Topo sheets: Otis - dam site

Becket: north part of  
reservoir & drainage basin

### Drainage areas:

Dam: 1.322 sq. mi from project plans.

1.3 sq. mi from check

Route 20 crossing - 5000 ft. downstream from dam

add. 0.67 sq. mi

Total 1.99 sq. mi

2<sup>nd</sup> Route 20 crossing - 1500 ft. down stream from

Walker Brook junction

4.2 sq. mi.

4.2

Total 10.3 sq. mi



U-19-24

11/26/79

Moe  
chk'd DNL

## Indian Lake Dam

1.2 c. size classification: (Table 1)

Top of storage = top of dam = 2480.0

Natural channel at downstream toe = 1465.3

Height

14.7'

Height  $< 40'$  is SMALL class.

Impoundment:

Bottom to normal W.L. = 256 ac. ft.

Normal W.L. to Flood W.L. = 140  
346

Flood W.L. to top of Dam = 225

Maximum storage = 621 ac. ft.

Storage  $\leq 1000$  ac. ft. is SMALL class

# Indian Lake Dam Reservoir Volume

U. 19-29  
11/5/79  
MOE.  
chkd DML

Elev MSL	Area Ac.	h ft.	Δ Vol. Ac. ft	Cumulative Volume Design
1465	0			0
1468	<del>23.4</del>	5	39	
1470	23.4	3	104	44
1473	46.2	2	108	148
1475	" 62 "	2	132	256
1477	" 70 "	2		140
			225	396
1480	80	3		621
1485	94	5	435	1056

U-19-24  
11/6/79  
MOE  
CH&DNL

# Indian Lake Dam Outlet Works capacity.

Spill way: free overfall, straight drop.

Filled for flashboards to elev. 1478.5

Fixed conc. crest elev. elev. 1473.0

Piers & sidewalls suppress end contractions.

Vertical concrete face acts as sharp edge weir.

Francis formula:  $Q = 3.33 L H^{3/2}$ ;  $H = (Q/3.33L)^{2/3}$

Length = 3. cat. 5'-4" = 16.00'

	Design max above normal WL	Design Max above conc. crest	Low embankment Flash boards as found	Design flood above Normal W.L.	Design Dam top above Max stop logs	Dam top above Max stop logs	Dam top above conc. crest	Test Flood above conc. crest	Top of dam above normal W.L.
Top	1480.0	1480.0	1479.9	1477.0	1480.0	1478.9	1478.9	1479.55	1478.9
Crest	1475.0	1473.0	1474.4	1475.0	1478.5	1478.5	1473.0	1473.0	1475.1
H(H)	5.0	7.0	4.5	2.0	1.5	0.4	5.9	6.55	3.9
Q(cfs)	595	987	508	140	98	13.5	265	894	410

Reservoir drain: 30" x 30" sluice gate = Rodney Hunt Hy &

Rodney Hunt formula:  $Q = 0.70 A \sqrt{2gH} = 351 \sqrt{H}$


2 sluice gate =  $1466.6 + 2.5/2 = 1466.9$

H(H.)	13.1	13.1	12.0	13.1	12.0	12.65	12.1
Q(cfs)	127	127	121	127	121	125	121
Total Q	722	1114	629	167	886	1019	531

# STAGE - CAPACITY

Moe

INDIAN LAKE DAM



HYDROLOGIC COMPUTATIONS

MAXIMUM PROBABLE FLOOD

RESERVOIR ROUTING

## SPILLWAY TEST FLOOD

MOC

INDIAN LAKE DAM

Drainage area = 845 acres = 1.32 sq. mi. < 2 sq. mi.  
 Extrapolate MPF to 1.32 sq. mi.

Terrain is gently rolling

Good forest cover

Upstream swamps

95% to 98%  
 41+ acres.

Dam size = SMALL

Dam Hazard = more than a few = HIGH

Spillway Test Flood =  $\frac{1}{2}$  PMF to PMF

Use  $\frac{1}{2}$  PMF

$$Q_{PMF\frac{1}{2}} = \frac{1.32}{2} (2250) = 1485 \text{ cfs.}$$

Reduction for upstream swamps: Area = 41 Ac. at 0' depth

$$STOR = \left( \frac{41 + 45}{2} (2) / 845 \right) 12 = 1.2''$$

$$Q'_{PMF\frac{1}{2}} = 1485 \left( 1 - \frac{1.2}{12} \right) = 1300 \text{ cfs.}$$

Reduce Q for good forest cover  
 gentle rolling slopes

say 10%

$$Q''_{PMF\frac{1}{2}} = 1300 (.90) = 1170 \text{ cfs.} = \text{Indian Lake Inflow}$$

$$\text{Spillway head required} = H_1 = (1170 / 16 (3.33))^{\frac{2}{3}} = 7.84$$


$$\text{Top of Dam above spillway crest} = \underline{7.0'}$$

$$\text{Dam over topped by } 0.84'$$

Route Spillway Test Flood thru reservoir.

# MAXIMUM PROBABLE FLOOD PEAK FLOW RATES

x 5 - NED DAM IDENTIFICATION  
 ⊗ 7' - TWICE SPF AT INDICATED SITES  
 DEC. 1977



## Reservoir Routing

Assume Flood storage starts at Normal Pool  
Flash board go out; spillway capacity above Elev. 1473.0

Elev. = 1475 Reservoir capacity = 256 Ac.ft. = 3.64 in.

$$Q_{p1} = 1266 \text{ cfs}$$

$$H_1 = (1266/1613.33)^{2/3} = 8.27'$$

$$\text{Elev.} = \frac{1473}{1481.27}'$$

Reservoir capacity = 723 Ac.ft.

$$STOR_1 = \left( \frac{723 - 256}{845} \right) 12 = 6.63$$

$$Q_{p2} = 1266 \left( 1 - \frac{6.63}{9.5} \right) = 382.2 \text{ cfs.}$$

Try Elev. 1478

$$H = 5.0' \quad Q = 596 \text{ cfs} \quad STOR = \left( \frac{469 - 256}{845} \right) 12 = 3.02 \text{ in.}$$

$$Q_{p2} = 1266 \left( 1 - \frac{3.02}{9.5} \right) = 863 \text{ cfs.}$$

Try Elev. 1478.8

$$H = 5.8' \quad Q = 744 \text{ cfs} \quad STOR = \left( \frac{528 - 256}{845} \right) 12 = 3.86 \text{ in.}$$

$$Q_{p2} = 1266 \left( 1 - \frac{3.86}{9.5} \right) = 751 \text{ cfs.} \cong 744 \text{ cfs}$$

## CONCLUSIONS:

Spillway and Reservoir have adequate capacity  
if flash boards go out early.



HYDRAULIC COMPUTATIONS

DAM FAILURE

FLOOD WAVE ROUTING

# DAM FAILURE

Moe INDIAN LAKE DAM

Situation at failure:

Reservoir at elevation at Spillway test Flood  
Reservoir stage Elev: 1478.8

Reservoir capacity 528 Ac. ft.

Spillway discharge 750 cfs.

Storm on watershed =  $\frac{1}{2}$  MPF

Effective on watershed below dam at runoff  
rate (csm) of total watershed including I.L. Dam.

Failure flow:

Breach width = 40% length at mid height - spillway

Mid height =  $(1480.0 + 1465.6) / 2 = 1472.8$

Length at Elev 1472.8 = 260'

Breach width =  $(260' - 27') \cdot 4 = (233') \cdot 4 =$

Height  $Y_0 = 1478.8 - 1465.6 = 13.2'$

$$Q_{P1} = \frac{8}{27} W_b \sqrt{g} Y_0^{3/2} = \frac{8}{27} (233) \sqrt{32.2} (13.2)^{3/2} (40) = \underline{7515 \text{ cfs}}$$


# DAM FAILURE

MOE

INDIAN LAKE DAM

## ① BONNY RIGG HILL ROAD

Bridge 1



### Culvert Flow

Assume head differential = 3.0' due to tailwater effect.

Due to clogging only entrance loss is significant

$$Q_c = (.30) A \sqrt{2gH} = .30(2) \pi 2.25^2 \sqrt{2 \cdot 3.0} = 133 \text{ cfs.}$$

### Flow over road

200' wide broad crested weir

$$Q_R = 3.0 L H^{3/2} = 600 H^{3/2}$$

Elev	H	$Q_R$	$Q_c$	$Q_T$
1471.52	1.02	618	133	750
1475.0	4.5	5727	133	5860
1476.0	5.5	7739	133	7872

### Valley inundation


	Elev.	Ave. width ft.	Area Ac.	V Ac ft.	
Reach length = 600'	1470	180	2.5	6.25	1.25 Ac ft./ft.
	1475	320	4.4	23.50	3.45 Ac ft./ft.

# DAM FAILURE

## ① BONNY RIGG HILL ROAD

CHAD UHL V 17-21

MOB INDIAN LAKE DAM



$$Q_1 = 7515 \text{ cfs} \quad \text{Elev.} = 1475.88 \quad V = 27.1 \text{ Ac ft.}$$

$$Q_0 = 750 \text{ cfs} \quad \text{Elev.} = 1471.52 \quad V = 10.6 \text{ Ac ft.}$$

$$Q_{p2T} = (7515 - 750) \left( 1 - \frac{27.1 - 10.6}{52.8} \right) = 6553 + 750 = 7304 \text{ cfs.}$$

$$Q_{p2T} = 7304 \text{ cfs} \quad \text{Elev.} = 1475.75 \quad V = 26.2$$

$$V_{ave} = \frac{27.1 + 26.2}{2} - 10.6 = 16.05$$

$$Q_{p2} = 750 + (7515 - 750) \left( 1 - \frac{16.05}{52.8} \right) = 750 + 6560 = 7310 \text{ cfs.}$$

$$\text{Elev.} = 1475.75$$

$$\text{Depth over road} = \frac{2}{3} (1475.75 - 1471.5) = 2.83 \text{ ft}$$

$$\text{Velocity over road} = \sqrt{(2.83/2) 2g} = 9.55 \text{ fps.}$$

Before dam failure

$$\text{Depth over road} = (\frac{2}{3}) 1.02 = 0.68 \text{ ft}$$

$$\text{Velocity over road} = \sqrt{(0.68/2) 2g} = 4.68 \text{ fps}$$

# DAM FAILURE

# MOC INDIAN LAKE DAM


## ② Route US20

Reach length = 6400 ft

$$S = 210/6500 = .030$$

$$R = .040$$

Bridge 2  
Typical Valley Section



$$A = 10y^2/2 + 5y + 25y^2/2 = 5y + 17.5y^2$$

$$P = 10.05y + 5 + 25.02y = 5 + 35.07y$$


$$R = A/P$$

$$Q = \frac{1.49}{n} AR^{2/3} S^{1/2} = 6.495 AR^{2/3}$$

$$y = 5'; A = 462.5; P = 180.35; R = 2.564; Q = 5628 cfs$$

$$y = 7'; A = 892.5; P = 250.5; R = 3.563; Q = 13,523 cfs$$

$$y = 2'; A = 80; P = 75.14; R = 1.065; Q = 542 cfs$$



Valley storage:  $V_v = A \frac{6400}{45500}$

$$y = 3' \quad V_v = 25.3 \quad V_s = 7.1 \quad V_T = 32.4$$

$$y = 5' \quad V_v = 67.9 \quad V_s = 19.4 \quad V_T = 87.3$$

$$y = 7' \quad V_v = 131.1 \quad V_s = 22.8 \quad V_T = 154$$

Swamp Storage

$y_H$	$L_H$	$W_H$	AAC.	V
0	800	200	3.67Ac	0
3	850	300	5.85	14.28
13	1000	380	8.72	72.85
5			6.42	12.27
7			7.00	13.42
				39.9

## DAM FAILURE

Mic

INDIAN LAKE DAM

(2) Spark Brook at U.S. Route 20

Bridge (2)

Drainage Area: Dam O.A. = 845 Ac. = 1.32 Sq. Mi.

Spark Brook below dam	$\frac{480}{1275 \text{ Ac.}}$	$\frac{.67}{1.99 \text{ Sq. Mi.}}$
-----------------------	--------------------------------	------------------------------------

MPF: Rolling terrain; 1.99 sq. mi = 2130 cts/sq. mi.

Before fail

After fail

Runoff below dam

 $0.67 (2130/2) =$ 

714 cts.

714 cts.

From dam

Total

$$\begin{array}{r} 750 \\ 1464 \text{ cts} \end{array}$$

$$\begin{array}{r} 7310 \\ 8024 \text{ cts} \\ - 1464 \\ \hline 6560 \end{array}$$
 $Q_b = 1464 \text{ cts}; \quad V = 14.3 \text{ Ac. ft.}$  $Q_{p1} = 8024 \text{ cts}; \quad V = 31.4 \text{ Ac. ft.}$  $Q_{p2T} = 7812 \text{ cts}; \quad V = 30.9 \text{ Ac. ft.} \quad V_{av.} = (31.4 + 30.9)/2 = 31.15$ 

$$Q_{p2T} = 1464 + 6560 \left(1 - \frac{31.4 - 14.3}{52.0}\right) = 1464 + 6348 = 7812 \text{ cts}$$

$$Q_{p2} = 1464 + 6560 \left(1 - \frac{31.15 - 14.3}{52.0}\right) = 1464 + 6350 = 7815 \text{ cts.}$$

② U.S. Route 20 over Spark Brook

Bridge 2


Spark Brook Bridge

12' wide box culvert

60' downstream from 4' high stone dam

No storage at dam.

Culvert length = 46'



$$\text{Losses} = \text{Entrance} + \text{Friction} + \text{Exit}$$

$$H = 0.5 \frac{V^2}{2g} + 0.1 \frac{V^2}{2g} + 0.9 \frac{V^2}{2g} = 1.5 \frac{V^2}{2g}$$

$$Q = AV = 12(6.4) \sqrt{\frac{2g(6.5)}{1.5}} = 1285 \text{ cfs}$$

This is the maximum culvert capacity because of tailwater rise as head water rises above road

Flow over road as a broad crested weir

$$Q = 3.0 L H^{3/2} = 900 H^{3/2}$$

$$\text{Before failure } Q = 1464 \text{ cfs}$$

$$H = [(1464 - 1285)/900]^{2/3} = 0.34'$$

$$\text{Depth of flow} = \frac{2}{3}(0.34) = 0.23'$$

$$\text{Velocity} = \sqrt{2g(0.34/3)} = 2.7 \text{ fps}$$

$$\text{After failure } Q = 7815 \text{ cfs}$$

$$H = [(7815 - 1285)/900]^{2/3} = 3.75'$$

$$\text{Depth of flow} = \frac{2}{3}(3.75) = 2.50'$$


$$\text{Velocity} = \sqrt{2g(3.75/3)} = 9.0 \text{ fps.}$$

## (2A) Spark Brook at Walker Brook

Typical Valley Section  
 Reach length = 1000'

$$M = 0.040$$

$$S = 20/550 = .036$$



$$A = 20y^{3/2} + 5y + 10y^{3/2} = 5y + 15y^2$$

$$P = 20.02y + 5 + 10.05y = 5 + 30.07y$$


$$R = A/P$$

$$Q = \frac{1.5}{n} A R^{2/3} S^{1/2} = 7.115 A R^{2/3}$$

$$y = 2'; A = 70^{ft^2}; P = 66.4'; R = 1.05'; Q = 515 cfs; V = 1.61 Ac.H.$$

$$y = 5'; A = 400^{ft^2}; P = 150.5'; R = 2.524'; Q = 5275 cfs; V = 9.18 Ac.H.$$

$$y = 6'; A = 570^{ft^2}; P = 189.2'; R = 3.013'; Q = 8,460 cfs; V = 13.09 Ac.H.$$



Before failure:  $Q = 1464 cfs$ ;  $V = 3.39 Ac.H.$

After failure:  $Q = 7815 cfs$ ;  $V = 12.6 Ac.H.$

$$Q_{p2} = 1464 + 6351 \left( 1 - \frac{12.6 - 3.4}{528} \right) = 1464 + 6240 = 7704 cfs; V = 12.5$$

$$Q_{p2} = 1464 + 6351 \left( 1 - \frac{12.55 - 3.4}{528} \right) = 1464 + 6241 = 7705 cfs.$$



# DAM FAILURE

LAKE WALKER

Moe

INDIAN LAKE DAM

2

③ & ④ Walker Brook

Bridges 3 & 4

Drainage Area: Spark Brook below Dam

0.67 sq. mi.

Walker Brook

8.43 sq. mi.

9.10 sq. mi.

Indian Lake Dam

1.32

10.42 sq. mi.

MPF: Rolling terrain; 10.42 sq. mi.;  $Q = 1625 \text{ csm}$

Before failure      After failure

Runoff below dam  $\frac{1}{2}$  MPF

$9.10 (1625/2) =$

7394 cfs

7394 cfs.

From dam

750

750

6351

8144 cfs

14,495 cfs

44 SHEETS  
50 SHEETS  
88 SHEETS  
120 SHEETS  
142 SHEETS  
164 SHEETS  
186 SHEETS  
208 SHEETS  
230 SHEETS  
252 SHEETS  
274 SHEETS  
296 SHEETS  
318 SHEETS  
340 SHEETS  
362 SHEETS  
384 SHEETS  
406 SHEETS  
428 SHEETS  
450 SHEETS  
472 SHEETS  
494 SHEETS  
516 SHEETS  
538 SHEETS  
560 SHEETS  
582 SHEETS  
604 SHEETS  
626 SHEETS  
648 SHEETS  
670 SHEETS  
692 SHEETS  
714 SHEETS  
736 SHEETS  
758 SHEETS  
780 SHEETS  
802 SHEETS  
824 SHEETS  
846 SHEETS  
868 SHEETS  
890 SHEETS  
912 SHEETS  
934 SHEETS  
956 SHEETS  
978 SHEETS  
1000 SHEETS



## Walker Brook

## Typical Valley Section

From Spork Brook past bridge #8

$$n = 0.060 \quad s = 50/1600 = .031$$

$$Y \leq 10'$$


$$A = 2Y^2/2 + 20Y + 2Y^2/2 = 20Y + 2Y^2$$

$$P = 2.24Y + 20 + 2.24Y = 20 + 4.47Y$$

$$R = A/P$$

$$Q = \frac{1.5}{n} AR^{2/3} S^{1/2} = 4.40 AR^{2/3}$$

$$Y = 9; A = 342'; P = 60.23'; R = 5.68'; Q = 4790; V = \frac{AL}{43560} = 39.3 \text{ Ac. Ft.}$$



$$Y' \quad \text{Length of reach} = 13,000 - (7,000 + 1,000) = 5,000' = L$$

$$A = 2Y'^2/2 + (20)Y' + 10(20) + 10(20/2) + 40Y' + 1.43Y'^2 = 400 + 40Y' + 1.71Y'^2$$

$$P = 2.24Y' + 20 + 2.24 + 40 + 1.74Y' = 82.4 + 3.98Y'$$

$$R = A/P$$


$$Y' = 1'; A = 44.7'; P = 86.38'; R = 5.11'; Q = 5768 \text{ cfs}; V = 50.7 \text{ Ac. Ft.}$$

$$Y' = 2'; A = 486.8'; P = 90.20'; R = 5.40'; Q = 6591 \text{ cfs}; V = 55.9 \text{ Ac. Ft.}$$

$$Y' = 5'; A = 642.8'; P = 102.30'; R = 6.28'; Q = 9630 \text{ cfs}; V = 73.8 \text{ Ac. Ft.}$$

$$Y' = 8'; A = 829.4'; P = 114.24'; R = 7.26'; Q = 13,684 \text{ cfs}; V = 95.2 \text{ Ac. Ft.}$$

$$Y' = 10'; A = 971.0'; P = 122.20'; R = 7.95'; Q = 17,020 \text{ cfs}; V = 111.5 \text{ Ac. Ft.}$$



$$Y' = 12'; A = 1126'; P = 130.2'; R = 8.65'; Q = 20,883 \text{ cfs}; V = 129.3 \text{ Ac. Ft.}$$

## WALKER BROOK

Before failure:  $Q = 8,144 \text{ cfs}$ ;  $V = 65.8 \text{ ActH}$ .After failure:  $Q = 14,500 \text{ cfs}$ ;  $V = 98.2 \text{ ActH}$ .

$$Q_{p2r} = 8,144 + 6,356 \left(1 - \frac{98.2 - 65.8}{52.8}\right) = 8,144 + 5,966 = 14,110 \text{ cfs}; V = 96.5; V_{AV} = 97.4$$

$$Q_{p2} = 8,144 + 6,356 \left(1 - \frac{97.4 - 65.8}{52.8}\right) = 8,144 + 5,976 = 14,120 \text{ cfs}$$

## Route 20 Bridge 3

Distance from dam = 10,000'

Distance from Spark Brook = 2,000'


Length of waterway = 80'

bottom slope  $S = .03$  $n = .02$ 

$$A = 11(20) + \frac{1}{2}(20) = 327 \text{ ft}^2$$

$$P = 2(20) + 2(11) = 78 \text{ ft}$$

$$R = 327 / 78 = 4.2 \text{ ft}$$



Loss = Entrance + Friction + Exit

$$H = 0.5 \frac{V_1^2}{2g} + 0.2 \frac{V_2^2}{2g} + 1.0 \frac{V_2^2}{2g}$$

$$= 0.5 \frac{V_2^2 - 17^2}{64.4} + 0.2 \frac{V_2^2}{64.4} + \frac{V_2^2 - 17^2}{64.4}$$

$$= \frac{V_2^2}{129} - \frac{17^2}{129} + \frac{V_2^2}{322} + \frac{V_2^2}{64.4} - \frac{17^2}{64.4}$$

$$= (.00775 + .00311 + .01553) V_2^2 - 2.24 - 4.488$$

$$6.0 = .02638 V_2^2 - 6.728$$

$$V_2^2 = \sqrt{12.728 / .0264} = 22 \text{ fps}$$

$$Q = AV = 327(22) = 7182 \text{ cfs}$$

Flow over Road:

$$\text{Before failure } H = [(8,144 - 7182) / 3.0(120)]^{2/3} = 1.93'$$

$$\text{Depth} = \frac{2}{3}(1.93) = 1.28'$$

$$\text{Velocity} = \sqrt{2g(1.93/3)} = 6.4 \text{ fps}$$

$$\text{After failure: } Q = 14,500 - \frac{2000}{5000}(380) = 14,350 \text{ cfs}$$

$$H = [(14,350 - 7182) / 3.0(120)]^{2/3} = 7.35'$$

$$\text{Depth} = \frac{2}{3}(7.35) = 4.90'$$

$$\text{Velocity} = \sqrt{2g(7.35/3)} = 12.6 \text{ fps}$$


# DAM FAILURE

CHKD DmL V-17-24

Moo INDIAN LAKE DAM

## Walker Brook Bridge #4 Route 20

Length of waterway = 77'  
bottom slope = .03'  
 $n = .025$



$$A = [5.8 + \frac{2}{3}(8)] 27 = 171$$

$$P = 27 + 2(5.9) = 38.8'$$

$$R = A/P = 171/38.8 = 4.4$$

$$V = \frac{1.49}{n} R^{\frac{2}{3}} S^{\frac{1}{2}} = \frac{1.49}{.025} (4.4)^{\frac{2}{3}} (.03)^{\frac{1}{2}} = 28 \text{ fps}$$

$$H_v = V^2/2g = 28^2/64.4 = 12.2' > 5.6' = 11.2 - 6.6$$

This culvert will operate under inlet control.

$$\text{Approach velocity} = Q/A = 8144/571 = 14.3 \text{ fps}$$

$$\text{Inlet velocity } V = 14.3 + \sqrt{2g(5.6/1.5)} = 14.3 + 15.5 = 29.8 \text{ fps}$$

$$Q = AV = 171(28) = 4788 \text{ cfs}$$

## Flow over road

$$\text{Before failure: } Q = 8144 \text{ cfs}$$

$$H = [(8144 - 4788)/3.0(200)]^{\frac{2}{3}} = 3.15'$$

$$\text{Depth} = \frac{2}{3}(3.15) = 2.10'$$

$$\text{Velocity} = \sqrt{2g(3.15/3)} = 8.2 \text{ fps}$$

$$\text{After failure: } Q = 14,120 \text{ cfs}$$

$$H = [(14,120 - 4788)/3.0(200)]^{\frac{2}{3}} = 6.23'$$

$$\text{Depth} = \frac{2}{3}(6.23) = 4.15'$$

$$\text{Velocity} = \sqrt{2g(6.23/3)} = 11.6 \text{ fps}$$

## Walker Brook Route 20 at Bridge #5

Drainage area: Spark Brook	0.67 sq. mi.
Walker Brook	8.43
Walker Brook above Bridge #5	<u>4.80</u>
	13.98 sq. mi.
Indian Lake Dam	<u>1.32</u>
	15.30 sq. mi.

M.P.F. Rolling terrain; 15.3 sq. mi.;  $Q = 1520$  csm.

	Before failure	After failure
Runoff below dam $\frac{1}{2}$ MPF		
13.98 (1520/2) =	10,625 cfs	10,625 cfs

From dam	750	750
		<u>5,976</u>
Total flow $Q_{pi} =$	11,375 cfs	17,351 cfs

Before failure:  $Q = 11,375$  cfs;  $V = 82.7 \frac{3000}{5000} = 49.6$  Ac.H.After failure:  $Q = 17,350$  cfs;  $V = 113.0 \frac{3000}{5000} = 67.8$  Ac.H.
$$Q_{p2T} = 11,375 + 5976 \left( \frac{167.8 - 49.6}{52.8} \right) = 11,375 + 5770 = 17,145 \text{ cfs.}$$

$$V = 111.5 \frac{3000}{5000} = 67.8 \text{ Ac.H.}; V_{ave} = 67.0$$

# DAM FAILURE

INDIAN LAKE DAM

Bridge # 5, Route 20 over Walker Brook


Water way length = 71.5'  
 $S = .03$   $n = .025$

$$A = 25(7.5 + \frac{2}{3}(0.9)) = 202.5$$

$$P = 25.1 + 2(7.5) = 40.1$$

$$R = A/P = 202.5/40.1 = 5.05$$

$$V = \frac{1.49}{n} R^{2/3} S^{1/2} = 30.6 \text{ fps}$$



Check for inlet control:  $H = 5.0'$

$$H = \frac{1.5V_2^2 - V_1^2}{2g} \quad V = 14 + \sqrt{\frac{2gH}{1.5}} = 14 + 6.8 = 20.8 \text{ fps}$$

$$Q = AV = 202.5(20.8) = 4212 \text{ cfs.}$$

60" RCP

$n = .013$

$S = .03$

$V = 20 \text{ fps}$

$Q = 400 \text{ cfs}$

Flow over Road:

Before failure:  $Q = 11,375 \text{ cfs}$

$$H = \left[ \frac{11,375 - \frac{4600}{1.49}}{3.0(75)} \right]^{2/3} = 10.0' \quad 9.7'$$

$$\text{Depth} = \frac{2}{3}H = \frac{2}{3}(10.0) = 6.7' \quad 6.5'$$

$$\text{Velocity} = \sqrt{2g(\frac{10.0}{3})} = 14.6 \text{ fps.} \quad 14.4 \text{ fps}$$

After failure:  $Q = 17,145 \text{ cfs}$

$$H = \left[ \frac{17,145 - \frac{4600}{1.49}}{3.0(90)} \right]^{2/3} = 13.2' \quad 12.9'$$

$$\text{Depth} = \frac{2}{3}H = \frac{2}{3}(13.2) = 8.8' \quad 8.6'$$

$$\text{Velocity} = \sqrt{2g(13.2/3)} = 16.8 \text{ fps.} \quad 16.7 \text{ fps.}$$

# DAM FAILURE

INDIAN LAKE DAM

Bridge #6 Blandford Road over Walker Brook

Failure wave attenuation:

Before failure: Reach flow  $Q = 11,375 \text{ cfs}$ ;  $V = 82.7 \left( \frac{3000}{5000} \right) = 49.6 \text{ cfs}$

After failure: Reach flow  $Q = 17,145 \text{ cfs}$ ;  $V = 111.5 \left( \frac{3000}{5000} \right) = 66.9 \text{ cfs}$

$Q_{p27} = 11,375 + 5770 \left( 1 - \frac{66.9 - 49.6}{5.28} \right) = 11,375 + 5,580 = 16,955 \text{ cfs}$

$V = 111.2 \frac{3000}{5000} = 66.7$   $V_{wc} = \frac{66.9 + 66.7}{2} = 66.8$

Flows at Bridge #6

Drainage Area: D.A. Bridge 5 13.98 sq. mi.

Bridge 5 to 6 D.A. =  $\frac{1.68}{15.66} \text{ sq. mi.}$

Indian Lake Dam. D.A. =  $\frac{1.32}{16.98} \text{ sq. mi.}$

M.P.F. Rolling terrain 16.98 sq. mi.;  $Q = 1498 \text{ csm}$

	Before failure	After failure
Runoff below Dam $\frac{1}{2}$ M.P.F.		
$15.66 (1498/2) =$	11,730 cfs.	11,730 cfs

From dam	750	750
----------	-----	-----

Total flow $Q =$	$\frac{12,480 \text{ cfs}}$	$\frac{5,500}{18,060 \text{ cfs.}}$
------------------	-----------------------------	-------------------------------------

## DAM FAILURE

CHECK DATE V - - -

MOE INDIAN LAKE DAM

Blandford Road Bridge over Walker Brook Bridge

Waterway length = 36'

Bridge abutment length = 43'

 $S = .03$ ;  $n = .025$ 

$$A = 58(6.4) + \frac{58+25}{2}(1.5) + 25(1.5)^{2/3}$$

$$= 458 \text{ ft}^2$$

$$P = 58.2 + 7.9 + 6.4 = 72.50' ; R = A/P = 6.32'$$

Assume bridge will operate under inlet control

$$V = 14 + \sqrt{2g(2.4/15)} = 14 + 10.1 = 25 \text{ fps.}$$

$$Q = AV = 458(25) = 11,450 \text{ cfs.}$$

Flow over Road:

Before failure:

$$H = [(12,480 - 11,450)/3.0(100)]^{2/3} = 2.3'$$

$$\text{Depth} = 2/3(2.3) = 1.5'$$


$$\text{Velocity} = \sqrt{2g(2.3/3)} = 7.0 \text{ fps.}$$

After failure:

$$H = [(18,060 - 11,450)/3.0(100)]^{2/3} = 7.8'$$

$$\text{Depth} = 2/3(7.8) = 5.2'$$

$$\text{Velocity} = \sqrt{2g(7.8/3)} = 13.0 \text{ fps}$$



42 381 50 SHEETS 5 SQUARE  
42 382 100 SHEETS 5 SQUARE  
42 383 200 SHEETS 5 SQUARE





# DAM FAILURE

checked 1/14/2  
MOC INDIAN LAKE DAM

Failure wave attenuation to Hazard Area #7

Before failure:  $Q = 12,480 \text{ cfs}$ ;  $V = 91.3 \frac{3000}{5000} = 54.8 \text{ Ac.H.}$

Reach length = 3000'

After failure:  $Q = 18,060 \text{ cfs}$ ;  $V = 117.1 \frac{3000}{5000} = 70.3 \text{ Ac.H.}$

$Q_{p27} = 12,480 + 5,580 \left(1 - \frac{70.3 - 54.8}{520}\right) = 12,480 + 5,416 = 17,896 \text{ cfs.}$

$V = 116.6 \left(\frac{3000}{5000}\right) = 70 \text{ Ac.H.}$ ;  $V_{av} = (70.3 + 70.0)/2 = 70.1 \text{ Ac.H.}$

$Q_{p2} = 12,480 + 5,580 \left(1 - \frac{70.1 - 54.8}{520}\right) = 12,480 + 5,418 = 17,898 \text{ cfs.}$

Flows at Area #7: D.A. at Bridge #6: 15.66 sq. mi.  
#6 to #7 D.A. = 1.01

16.67 sq. mi.

Indian Lake Dam D.A. =

1.32

17.99 sq. mi.

M.P.F. Rolling terrain 17.99 sq. mi.;  $Q = 1475 \text{ csm}$

Runoff below dam  $\frac{1}{2}$  M.P.F. Before failure After failure

16.67 (1475/2) = 12,294 12,294

From dam

750

750

5,420

Total flow  $Q =$

13,044 cfs

18,464 cfs.

# DAM FAILURE

Moc

INDIAN LAKE DAM


## WALKER ISLAND CAMP GROUND

Harvard Area # 7

$$S = .03; m = .04$$

$$A = 6(2/2) + 2(20) + 10(2/2) + 10(4/2) + 30(4) + 4(3/2)4 + 208Y + 3Y^2/2 + 3Y^2/2$$

$$= 210 + 208Y + 3Y^2$$




$$P = 208.3 + 2(3.15Y) = 208.3 + 6.3Y; R = A/P; Reach length = 1000'$$

$$Y = 5'; A = 1250'; P = 239.8; R = 5.2'; Q = 24,429 cfs; V = 28.7 Ac ft.$$

$$Q = \frac{1.5}{m} A R^{2/3} S^{1/2} = \frac{1.5}{.04} .03^{1/2} A R^{2/3} = 6.50 A R^{2/3}; V = A / 43560 Ac ft.$$

$$Y = 3'; A = 861'; P = 227.2'; R = 3.79'; Q = 13,603 cfs; V = 19.8 Ac ft.$$

$$Y = 4'; A = 1090'; P = 233.5'; R = 4.67'; Q = 19,790 cfs; V = 25.0 Ac ft.$$



$$\text{Before failure } Q = 13,044 cfs; Y = 2.9'; V = 19.3 Ac ft.$$

$$\text{After failure } Q = 18,464 cfs; Y = 3.78'; V = 23.4 Ac ft.$$

$$Q_{P2} = 13044 + 5,420 \left(1 - \frac{23.4 - 19.3}{5.28}\right) = 13,044 + 5378 = 18,422 cfs; V = 23.4 Ac ft.$$

$$V_{ave} = (23.4 + 23.4) / 2 = 23.4 Ac ft = 23.4 Ac ft.$$

AD-A155 635

NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS  
INDIAN LAKE DAM (MA 0. (U) CORPS OF ENGINEERS WALTHAM  
MA NEW ENGLAND DIV DEC 79


2/2

UNCLASSIFIED

F/G 13/13

NL





MICROCOPY RESOLUTION TEST CHART  
NATIONAL BUREAU OF STANDARDS-1963-A

# DAM FAILURE

MOE INDIAN LAKE DAM

Town Road over Walker Brook Bridge #8

Dam break wave attenuation to Bridge #8

Before failure:  $Q = 13,044 \text{ cfs}$ ;  $V = 90.8 \frac{2000}{5000} = 36.3 \text{ A.H.}$

Reach length = 2000' from end of Hazard Area #7 to Bridge #8

After failure:  $Q = 18,422 \text{ cfs}$ ;  $V = 118.8 \frac{2000}{5000} = 47.5 \text{ A.H.}$

$Q_{P2T} = 13,044 + 5,378(1 - \frac{47.5 - 36.3}{52.8}) = 13,044 + 5264 = 18,308 \text{ cfs}$

$V = 118.2(\frac{2000}{5000}) = 47.2$ ;  $V_{ave} = (47.5 + 47.2)/2 = 47.4 \approx 47.5$

Flows at Bridge #8: D.A. @ #7 =

D.A. #7 to #8

D.A. below dam =

Indian Lake Dam

Total Area

16.67 sq. mi.

1.65

18.32 sq. mi.

1.32

19.64 sq. mi.

M.P.F. Rolling Terrain; D.A. = 19.64 sq. mi;  $Q = 1450 \text{ csm.}$

Runoff below Dam =  $\frac{1}{2}$  M.P.F.

$18.32(1450/2) =$

Before failure

13,282

After failure

13,282

From dam

750

750

5,264

Total flow  $Q =$

14,032 cfs

19,296 cfs.


# DAM FAILURE

Mo. INDIAN LAKE DAM

Town Road over Walker Brook

Bridge # 8

Bridge width = 14.2'  
 Abutment length = 18' ±  
 $S = .03$  ;  $n = 0.05$



$$A = 77(2.6) + \frac{77+30}{2}(5.2) + 30(\frac{2}{3})0.8$$

$$= 494.4$$

Assume inlet control

$$V = 14 + \sqrt{2g \cdot 3.4 / 1.5} = 14 + 12.1 = 26.1 \text{ fps.}$$

$$Q = VA = 26(494) = 12,844 \text{ cfs.}$$

Flow over Road :

Before failure  $Q = 14,032 \text{ cfs}$

$$H = [(14,032 - 12,844) / 3.0(100)]^{2/3} = 2.5'$$

$$\text{Depth} = \frac{2}{3}(2.5) = 1.7'$$

$$\text{Velocity} = \sqrt{2g(2.5/3)} = 7.3 \text{ fps.}$$

After failure  $Q = 19,300 \text{ cfs}$

$$H = [(19,300 - 12,850) / 3.0(100)]^{2/3} = 7.73'$$

$$\text{Depth} = \frac{2}{3}(7.73) = 5.2'$$

$$\text{Velocity} = \sqrt{2g(7.73/3)} = 12.9 \text{ fps.}$$

## Bridge #8 to Bridge #9

$$\text{Reach length} = 13,000'$$

$$S = 50/2100' = .024; n = .04$$

$$y = 10'$$

$$A = 6y^2/2 + 30y + 4y^2/2 = 30y + 5y^2$$

$$P = 6.08y + 30 + 4.12y = 30 + 10.2y$$

$$R = A/P; Q = 1.48 AR^{2/3} S^{1/2} = 5.81 AR^{2/3}$$

$$y = 10'; A = 800'; P = 132'; R = 6.06'; Q = 15,450 \text{ cfs}; V = 239 \text{ Ac.ft.}$$


$$y = 9'; A = 675'; P = 121.8'; R = 5.54'; Q = 12,282 \text{ cfs}; V = 201 \text{ Ac.ft.}$$

$$y' = y - 10'$$

$$A = 60(10/2) + 30(10) + 40(10/2) + 130y' + 10y'^2/2 = 800 + 130y' + 5y'^2$$

$$P = 132 + 6.08y + 10.05y' = 132 + 18.13y'$$

$$y' = 2'; A = 1080'; P = 168.3; R = 6.42'; Q = 21,672 \text{ cfs}; V = 322 \text{ Ac.ft.}$$



$$\text{Before failures } Q = 14,032 \text{ cfs}; V = 221 \text{ Ac.ft.}$$

$$\text{After failure: } Q = 19,300 \text{ cfs}; V = 290 \text{ Ac.ft.}$$

$$Q_{p2} = 14,032 + 5268 \left(1 - \frac{290 - 221}{528}\right) = 14,032 + 4580 = 18,612 \text{ cfs}; V = 221$$

$$V_{ave} = \frac{290 + 221}{2} = 255.5$$

$$Q_{p2} = 14,032 + 5268 \left(1 - \frac{255.5 - 221}{528}\right) = 14,032 + 4675 = 18,707 \text{ cfs}$$


## DAM FAILURE

INDIAN LAKE DAM

Route US 20 over Walker Brook in Chester Bridge #9

Waterway length, Average = 60'

$$n = .03$$

Assume bridge will operate  
under inlet controlEntrance loss with 45° wing walls =  $0.2 V^2 / 2g$ 

$$A = 32(9.3) + 32(2/3) = 320$$

$$V = V_1 + \sqrt{2g(3.5/2)} = V_1 + 13.7$$

At  $Q = 14,030 \text{ cfs}$ ;  $V_1 = 18.7 \text{ fps}$ . Bridge capacity =  $Q = AV$ 

$$Q_{\text{bridge}} = 320(32.4) = 10,370 \text{ cfs.}$$

At  $Q = 18,710 \text{ cfs}$ ;  $V_1 = 20.6 \text{ fps}$ .

$$Q_{\text{bridge}} = 320(34.3) = 10,976 \text{ cfs.}$$

Flow over road: Before failure

$$H = [(14,032 - 10,370) / 3.0(150)]^{2/3} = 4.04'$$

$$\text{Depth} = 2/3(4.04) = 2.7'$$

$$\text{Velocity} = \sqrt{2g(4.04/3)} = 9.3 \text{ fps.}$$

After failure

$$H = [(18,710 - 10,980) / 3(150)]^{2/3} = 6.66'$$

$$\text{Depth} = 2/3(6.66) = 4.44'$$

$$\text{Velocity} = \sqrt{2g(6.66/3)} = 12.0 \text{ fps.}$$



# DAM FAILURE

MOC

INDIAN LAKE DAM

## Westfield River in Chester, Mass

Drainage area = 64.7 sq. mi.

M.P.F. Rolling terrain; 64.7 sq. mi;  $Q = 1090$  csm

Runoff =  $(64.7 - 1.3) 1090 / 2 =$  Before failure At or failure  
34,553 cfs. 34,553 cfs.

From dam

750

750

Total flow.


35,303 cfs.

$\frac{750}{4675}$   
 39,978 cfs.

channel slope =  $30/3010 = .010$  ;  $n = .035$

$$A = 2Y^2 + 100Y + 2Y^2 = 100Y + 2Y^2$$

$$P = 2.24Y + 100 + 2.24Y = 100 + 4.48Y$$



$Y = 12'$ ;  $A = 1488$ ;  $P = 153.8$ ;  $R = 9.68$ ;  $Q = 29,000$  cfs.

$V = V_1 + \sqrt{2g(3/1.2)} = V_1 + 12.7$  fps.

$Q = AV = 1500(12.7 + 19.5) = 48,300$  cfs. = bridge capacity.


Channel capacity:



$Y = 15'$ ;  $A = 1950$ ;  $P = 167.2$ ;  $R = 11.67$ ;

$Q = 1.5 / .035 A R^{2/3} S^{1/2} = 42,900$  cfs.

Conclusions: This river channel & bridge is adequate for  $1/2$  M.P.F. + dam failure flood wave.

$Y = 10'$ ;  $A = 1200$ ;  $P = 144.8$ ;  $R = 8.3$ ;  $Q = 21,084$  cfs.





TIGHE & BOND / SCI CONSULTING ENGINEERS EASTHAMPTON, MASS.	U.S.ARMY ENGINEER DIV. NEW ENGLAND CORPS OF ENGINEERS WALTHAM, MASS.
NATIONAL PROGRAM OF INSPECTION OF NON-FED. DAMS	
LOCATION AND DOWNSTREAM HAZARD MAP	
INDIAN LAKE DAM (MA01051) BERKSHIRE COUNTY	BECKET MASSACHUSETTS
	SCALE: AS NOTED
	DATE: DECEMBER 1979

FLOOD EXPERIENCE

Reference: U.S.G.S. Water Supply Paper 1420  
 "Floods of August-October 1955"

Station	D.A.	cfs/mi <sup>2</sup>	cfs	Flow Duration Days	Rungff ft <sup>3</sup>	ac.ft.	in
Skyles Brook, Knightville	1.64	415	680	0.50	14.688x10 <sup>6</sup>	337	3.86
Walker Brook, Chester	17.7	295	5,220				
Stage Brook, Russell	5.21	942	4,910				
Potash Brook, Blandford	1.53	791	1,210				
Powermill Brook, Westfield	<u>2.50</u>	<u>2,300</u>	<u>5,740</u>				
Arithmetic Average		989					
Totals	28.58		17,760				
Weighted Average		621					

When applied to Indian Lake dam the following results:

Indian Lake, Becket	<u>1.32</u>	1,072	<u>1,415</u>	(design data underlined)			
	1.32	<u>415</u>	548		11.855x10 <sup>6</sup>	273	<u>3.86</u>
				(applicable Sykes Brook data underlined)			

Based on the 1955 flood report data, the design inflow peak and outflow peak are not unreasonable, but might be exceeded under some conditions.

APPENDIX E  
INFORMATION AS CONTAINED IN THE  
NATIONAL INVENTORY OF DAMS

# INVENTORY OF DAMS IN THE UNITED STATES

①	②	③	④	⑤	⑥	⑦	⑧	⑨	⑩	⑪	⑫	⑬	⑭	⑮	⑯	⑰	⑱	⑲	⑳	㉑	㉒	㉓	㉔	㉕	㉖	㉗	㉘	㉙	㉚	㉛	㉜	㉝	㉞	㉟	㊱	㊲	㊳	㊴	㊵	㊶	㊷	㊸	㊹	㊺	㊻	㊼	㊽	㊾	㊿
STATE	DIVISION	COUNTY	CITY	NAME	REPORT DATE	DAY	MO	YR	LATITUDE (NORTH)	LONGITUDE (WEST)	DIST FROM DAM (MI.)	POPULATION	TYPE OF DAM	YEAR COMPLETED	PURPOSES	STATUS	HYDRAULIC HEIGHT (FT.)	MAXIMUM CAPACITY (CU FT.)	MINIMUM CAPACITY (CU FT.)	NEAREST DOWNSTREAM CITY - TOWN - VILLAGE	POPULATION	REMARKS																											
MA	1051	NFD	MA 003 01	INDIAN LAKE DAM	03 JAN 80				4210.9	7301.5							15	15	539	CHESTER	0																												

POPULAR NAME		NAME OF IMPONDMENT	
		INDIAN LAKE	
REGION/DASH	RIVER OR STREAM	NEAREST DOWNSTREAM CITY - TOWN - VILLAGE	POPULATION
01 08	SPARKS BROOK	CHESTER	0

TYPE OF DAM	YEAR COMPLETED	PURPOSES	STATUS	HYDRAULIC HEIGHT (FT.)	MAXIMUM CAPACITY (CU FT.)	MINIMUM CAPACITY (CU FT.)	NEAREST DOWNSTREAM CITY - TOWN - VILLAGE	POPULATION
REPG	1975	R		15	15	539	CHESTER	0

REMARKS	

DIS HAS LENGTH	SPILLWAY TYPE	VOLUME OF DAM (CU FT.)	MAXIMUM DISCHARGE (FT.)	POWER CAPACITY (KW)	INSTALLED PROPOSED (KW)	NAVIGATION LOCKS
1	460 U	16	395			

OWNER	ENGINEERING BY	CONSTRUCTION BY
COMMUNITY SAVINGS BANK	BARNES + JARNIS	ANDREWS CONSTRUCTION

REGULATORY AGENCY	
DESIGN	CONSTRUCTION
OPERATION	MAINTENANCE

INSPECTION BY	INSPECTION DATE DAY MO YR	AUTHORITY FOR INSPECTION
TIGH + BOND / SCI	31 OCT 79	PL-92-367

REMARKS	

0187 OWN FED R PRV/PED SC9 A VER/DATE  
NED N N N N

**END**

**FILMED**

**7-85**

**DTIC**